


STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING						FORM 3 AMENDED REPORT <input type="checkbox"/>				
<b>APPLICATION FOR PERMIT TO DRILL</b>						1. WELL NAME and NUMBER Karren Trust 4-30C4				
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>						3. FIELD OR WILDCAT ALTAMONT				
4. TYPE OF WELL Oil Well Coalbed Methane Well: NO						5. UNIT or COMMUNITIZATION AGREEMENT NAME				
6. NAME OF OPERATOR EP ENERGY E&P COMPANY, L.P.						7. OPERATOR PHONE 713 997-5038				
8. ADDRESS OF OPERATOR 1001 Louisiana, Houston, TX, 77002						9. OPERATOR E-MAIL maria.gomez@epenergy.com				
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) Fee			11. MINERAL OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>			12. SURFACE OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>				
13. NAME OF SURFACE OWNER (if box 12 = 'fee') Glen A. Karren Family Living Trust						14. SURFACE OWNER PHONE (if box 12 = 'fee') 435-823-6355				
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee') PO Box 170, ,						16. SURFACE OWNER E-MAIL (if box 12 = 'fee')				
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')			18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>			19. SLANT VERTICAL <input checked="" type="checkbox"/> DIRECTIONAL <input type="checkbox"/> HORIZONTAL <input type="checkbox"/>				
20. LOCATION OF WELL	FOOTAGES		QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN			
LOCATION AT SURFACE	763 FNL 1733 FEL		NWNE	30	3.0 S	4.0 W	U			
Top of Uppermost Producing Zone	763 FNL 1733 FEL		NWNE	30	3.0 S	4.0 W	U			
At Total Depth	763 FNL 1733 FEL		NWNE	30	3.0 S	4.0 W	U			
21. COUNTY DUCESNE			22. DISTANCE TO NEAREST LEASE LINE (Feet) 769		23. NUMBER OF ACRES IN DRILLING UNIT 80					
			25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 2200		26. PROPOSED DEPTH MD: 11600 TVD: 11600					
27. ELEVATION - GROUND LEVEL 5804			28. BOND NUMBER 400JU0708		29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE Duchesne City					
<b>Hole, Casing, and Cement Information</b>										
String	Hole Size	Casing Size	Length	Weight	Grade & Thread	Max Mud Wt.	Cement	Sacks	Yield	Weight
Surf	12.25	9.625	0 - 2000	40.0	N-80 LT&C	0.0	Type V	412	2.36	12.0
							Class G	195	1.3	14.3
I1	8.75	7	0 - 8450	29.0	HCP-110 LT&C	10.2	Class G	590	1.91	12.5
							Class G	298	1.64	13.0
L1	6.125	5	8250 - 11600	18.0	HCP-110 LT&C	12.0	Class G	199	14.2	1.52
<b>ATTACHMENTS</b>										
<b>VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES</b>										
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER					<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN					
<input checked="" type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)					<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER					
<input type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)					<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP					
NAME Maria S. Gomez			TITLE Principal Regulatory Analyst			PHONE 713 997-5038				
SIGNATURE			DATE 02/12/2015			EMAIL maria.gomez@epenergy.com				
API NUMBER ASSIGNED 43013532680000			APPROVAL  Permit Manager							

**Karren Trust 4-30C4  
Sec. 30, T3S, R4W  
DUCHESNE COUNTY, UT**

**EP ENERGY E&P COMPANY, L.P.**

**DRILLING PROGRAM**

**1. Estimated Tops of Important Geologic Markers**

<u>Formation</u>	<u>Depth</u>
Green River (GRRV)	3,673' TVD
Green River (GRTN1)	4,361' TVD
Mahogany Bench	5,228' TVD
L. Green River	6,521' TVD
Wasatch	8,381' TVD
T.D. (Permit)	11,600' TVD

**2. Estimated Depths of Anticipated Water, Oil, Gas or Mineral Formations:**

<u>Substance</u>	<u>Formation</u>	<u>Depth</u>
	Green River (GRRV)	3,673' MD / TVD
	Green River (GRTN1)	4,361' MD / TVD
	Mahogany Bench	5,228' MD / TVD
Oil	L. Green River	6,521' MD / TVD
Oil	Wasatch	8,381' MD / TVD

**3. Pressure Control Equipment: (Schematic Attached)**

A Diverter Stack on structural pipe from 40' MD/TVD to 2,000' MD/TVD. A 10M BOP stack w/ rotating head, spacer spool, 5M annular, flex rams, blind rams & single w/ flex rams used from 2,000' MD/TVD to 8,450' MD/TVD. A 10M BOP stack w/ rotating head, spacer spool, 5M annular, flex rams, blind rams & single w/ flex rams from 8,450' MD/TVD to TD (11,600' MD /TVD).

The BOPE and related equipment will meet the requirements of the 5M and 10M system.

We have pre-set numerous wells around the proposed location and had no issues. The closest well is the Moon 3-30C4 which we Spud September of 2014 which is in the same section & less than ½ mile away. We got 60 bbls of cement back on the surface job & had full returns on the intermediate and liner cement jobs. I will design this proposed well the same way we designed the Moon 3-30C4.

There are 19 water wells within 10,000' of the proposed location but none of them are within 0.75 miles. This wellbore design is the same as the Moon 3-30C4.

There is 1 SWD well within 2.5 miles of the proposed location but none of them are within 1 mile. No pressure communication is expected to be seen, however it is important to be aware of them.

**The Blue Bench 1-13C5 SWD is 11,418' or 2.16 miles to the North / North West of the proposed location.** It is owned by Intercept Energy & is an active SWD well. It is injecting into the Upper/Middle Green River & Upper-most Lower Green River. The injection interval is from 4106'-7528'. The injection rate is now ~500 bbls/day @ 500-600 psi (I just got off the phone with Keith who is with Intercept Energy). The pressure dissipates to 300 psi while down on maintenance. Using 300 psi, the EMW @ 4106' is 10.01 ppg. We should not see any pressure from this well since it is Due South of the proposed location. We have drilled as close as 0.98 miles to this SWD well (that well is between the SWD & this proposed location) & **on fracture orientation** and have not seen any pressure while drilling. **If any pressure communication is seen, we can easily weight up to 10.1 ppg MW to control the wellbore. Our intermediate cement design will be 12.5 ppg lead & 13 ppg tail. We will also pump at least a 11.0 ppg weight spacer. We will also bring the cement up to surface instead of 500' into the shoe.**

#### **OPERATORS MINIMUM SPECIFICATIONS FOR BOPE:**

The surface casing will be equipped with a flanged casing head of 5M psi working pressure. An 11" 5M x 11" 10M spool, 11" x 10M psi BOP and 5M psi annular will be nipped up on the surface casing and tested to 250 psi low test / 3,000 psi high test for 10 minutes each prior to drilling out. The surface casing will be tested to 1,000 psi. for 30 mins. Intermediate casing will be tested to the greater of 1,500 psi or 0.22 psi/ft. The choke manifold equipment, upper Kelly cock and floor safety valves will be tested to 5M psi. The annular preventer will be tested to 250 psi low test / 4,000 psi high test. The 10M BOP will be installed with rotating head, spacer spool, 5M annular, flex rams, blind rams & single w/ flex rams from surface shoe to TD. The BOPE will be hydraulically operated.

In addition, the BOP equipment will be tested after running intermediate casing, after any repairs to the equipment and at least once every 30 days. Pipe and blind rams will be activated on each trip, annular preventer will be activated weekly and weekly BOP drills will be held with each crew.

#### **Statement on Accumulator System and Location of Hydraulic Controls:**

Precision Rig # 406 is expected to be used to drill the proposed well. Operations will commence after approval of this application. Manual and/or hydraulic controls will be in compliance with 5M and 10M psi systems.

**Auxiliary Equipment:**

- A) Pason Gas Monitoring 2,000' - TD
- B) Mud logger with gas monitor – 2,000' to TD (11,600' MD/TVD)
- C) Choke manifold with one manual and one hydraulic operated choke
- D) Full opening floor valve with drill pipe thread
- E) Upper and lower Kelly cock
- F) Shaker, de-sander and centrifuge

**4. Proposed Casing & Cementing Program:**

Please refer to the attached Wellbore Diagram.

All casing will meet or exceed the following design safety factors:

- Burst = 1.00
- Collapse = 1.125
- Tension = 1.2 (including 100k# overpull)

Cement design calculations for intermediate and production hole will be based on minimum 10% excess over gauge hole volumes. Actual volumes pumped will be a minimum of 10% excess over caliper volume to designed tops of cement for any section logged. A minimum of 50% excess over gauge volume will be pumped on surface casing.

**5. Drilling Fluids Program:**

Proposed Mud Program:

Interval	Type	Mud Weight
Surface	Air	Air
Intermediate	WBM	9.3 – 10.2
Production	WBM	10.5 – 12.0

Anticipated mud weights are based on actual offset well bottom-hole pressure data. Mud weights utilized may be somewhat higher to allow for trip margin and to provide hole stability for running logs and casing.

Visual mud monitoring equipment will be utilized.

6. **Evaluation Program:**

Logs:

Mud Log: 2,000' MD/TVD – TD (11,600' MD/TVD)

Open Hole Logs: Gamma Ray, Neutron-Density, Resistivity, Sonic, from surface casing shoe to TD.

7. **Abnormal Conditions:**

Maximum anticipated bottomhole pressure calculated at 11,600' TVD equals approximately 7,238 psi. This is calculated based on a 0.624 psi/ft gradient (12.0 ppg mud density at TD).

Maximum anticipated surface pressure equals approximately 4,686 psi (bottomhole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/ft).

Maximum anticipated surface pressure based on frac gradient at 7" casing shoe is 0.8 psi/ft at 8,450' TVD = 6,760 psi


BOPE and casing design will be based on the lesser of the two MASPs which is 4,686 psi.

8. **OPERATOR REQUESTS THAT THE PROPOSED WELL BE PLACED ON CONFIDENTIAL STATUS.**



## Drilling Schematic

<b>Company Name:</b> EP ENERGY	<b>Date:</b> February 11, 2015
<b>Well Name:</b> Karren Trust 4-30C4	<b>TD:</b> 11,600
<b>Field, County, State:</b> Altamont, Duchesne, Utah	<b>AFE #:</b> TBD
<b>Surface Location:</b> Sec 30 T3S R4W 763' FNL 1733' FEL	<b>BHL:</b> Straight Hole
<b>Objective Zone(s):</b> Green River, Wasatch	<b>Elevation:</b> 5803.8
<b>Rig:</b> Precision 406	<b>Spud (est.):</b> TBD
<b>BOPE Info:</b> Diverter System from 40' to 2,000' . 11 10M BOPE w/ rotating head & 5M annular from 2,000' to 8,450' . 11 10M BOPE w/ rotating head, spacer spool, 5M annular, flex rams, blind rams, single w/ flex rams from 8,450' to TD	



**DRILLING PROGRAM**

CASING PROGRAM	SIZE	INTERVAL		WT.	GR.	CPLG.	BURST	COLLAPSE	TENSION
SURFACE	9-5/8"	0	2000	40.00	N-80	LTC	5,750	3,090	737
INTERMEDIATE	7"	0	8450	29.00	HCP-110	LTC	11,220	9,750	797
PRODUCTION LINER	5"	8250	11600	18.00	HCP-110	STL	13,940	15,450	341

CEMENT PROGRAM		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE	Lead	1,500	EXTENDACEM SYSTEM: Type V Cement + 2% Cal-Seal + 0.35% Versaset + 0.3% D-Air 5000 + 6% Salt + 2% Econolite + 0.125 Poly-E-Flake	412	100%	12.0 ppg	2.36
	Tail	500	HALCEM SYSTEM: Class G Cement + 3 lbm/sk Silicalite Compacted + 1% Salt + 0.3% Econolite + 0.25 lbm/sk Poly-E-Flake + 0.25 lbm/sk Kwik Seal + 0.3% D-AIR 5000	195	50%	14.3 ppg	1.30
INTERMEDIATE	Lead	6,000	EXTENDACEM SYSTEM: Class G Cement + 6% Bentonite + 0.2% Econolite + 0.3% Versaset + 0.75% HR-5 + 0.3% Super CBL + 0.2% Halad-322 + 0.125 lb/sk Poly-E-Flake	590	35%	12.5 ppg	1.91
	Tail	2,450	EXPANDACEM SYSTEM: Class G Cement + 4% Bentonite + 0.25 Poly-E-Flake + 0.1% Halad-413 + 5 lb/sk Silicalite Compacted + 0.15% SA-1015 + 0.3% HR-5	298	30%	13.0 ppg	1.64
PRODUCTION LINER		3,350	EXTENDACEM SYSTEM: Class G Cement + 0.2% Super CBL + 0.3% Halad 344 + 0.3% Halad 413 + 5 lb/sk Silicalite + 20% SSA-1 + 2% Bentonite + 0.7% HR-5	199	30%	14.2 ppg	1.52

FLOAT EQUIPMENT & CENTRALIZERS	
SURFACE	PDC drillable guide shoe, 1 joint casing, PDC drillable float collar. Thread lock all float equipment. Install bow spring centralizers on the bottom 3 joints of casing & every 3rd joint thereafter.
INTERMEDIATE	Halliburton's PDC drillable 10M, P-110 float shoe, 1 joint, PDC drillable 10M, P-110 float collar. Thread lock all float equipment. Maker joint at +/- 6,500'.
LINER	Float shoe, 1 joint, float collar, 1 joint, landing collar. Thread lock all FE. Maker joints every 1000'.

PROJECT ENGINEER(S): Brad MacAfee 713-997-6383

MANAGER: Bob Dodd



**KARREN TRUST 4-30C4**  
**WELL LOCATION: NW/NE SECTION 30, T.3S, R.4W. U.S.B.&M.**  
**DUCHESNE COUNTY, UTAH**

PROCEED IN A NORTHERLY DIRECTION FROM DUCHESNE, UTAH ALONG STATE HIGHWAY 87 APPROXIMATELY 3.2 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ACCESS ROAD TO THE EAST; TURN RIGHT AND PROCEED IN A SOUTHEASTERLY DIRECTION APPROXIMATELY 0.4 MILES TO THE JUNCTION OF THIS ROAD AND THE PROPOSED ACCESS ROAD TO THE SOUTH; TURN RIGHT AND FOLLOW ROAD FLAGS IN A SOUTHERLY THEN SOUTHEASTERLY DIRECTION APPROXIMATELY 3,651 FEET TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM DUCHESNE, UTAH TO THE PROPOSED LOCATION IS APPROXIMATELY 3.6 MILES.

CONFIDENTIAL



**OUTLAW**  
**ENGINEERING INC.**

P.O. BOX 1800  
ROOSEVELT, UTAH 84066  
(435) 232-4321

RECEIVED: February 12, 2015





# KARREN TRUST 4-30C4

WELL LOCATION: NW/NE SECTION 30, T.3S, R.4W, U.S.B.&M.  
DUCHESNE COUNTY, UTAH




Photo: View of location stake

Camera Angle: Southwesterly



Photo: View from beginning of proposed access

Camera Angle: Southerly



**OUTLAW  
ENGINEERING INC.**

P.O. BOX 1800  
ROOSEVELT, UTAH 84066  
(435) 232-4321

PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY OUTLAW  
ENGINEERING, INC. AND MAY NOT REFLECT ACTUAL LOCATION OF PROPERTY LINES.

## Location Photos

VERSION:	V2
SURVEYED:	12-17-14



DEC 27, 2014  
AUTHOR: BWH

**PHOTO**



RECEIVED: February 12, 2015



# PROPOSED LOCATION LAYOUT

## KARREN TRUST 4-30C4

WELL LOCATION: NW/NE SECTION 30, T3S, R4W, U.S.B.&M.  
DUCESNE COUNTY, UTAH



—	EXISTING CONTOURS	2	CORNER NUMBER
—	PROPOSED CONTOURS	F+5.7	CUT/FILL NUMBER
- - -	LIMITS OF DISTURBANCE	EL. 5860.8'	EXISTING GRADE
-x-	EXISTING FENCE		PROPOSED WELL LOCATION
- - -	DIVERSION DITCH		

**SUMMARY**  
EXISTING GRADE @ CENTER OF WELL = 5805.3'  
FINISH GRADE ELEVATION = 5803.8'  
CUT SLOPES = 1.5 : 1  
FILL SLOPES = 1.5 : 1  
TOTAL WELL PAD AREA = 2.96 ACRES  
TOTAL WELL PAD DISTURBANCE AREA = 4.40 ACRES

\*RESERVE PIT\*  
8' & 12' DEEP, SEE ABOVE  
SLOPE 1.5:1  
PIT VOL. = 3,890 CY

## PROPOSED LOCATION LAYOUT KARREN TRUST 4-30C4

WELL LOCATION: NW/NE SECTION 30, T3S, R4W, U.S.B.&M.  
DUCESNE COUNTY, UTAH




**PAD/PIT  
GRADING**

DECEMBER 24, 2014  
SCALE: 1" = 80'  
DESIGN: MARFII DRAWN: JMH

SHEET NO.  
**2**







**OUTLAW  
ENGINEERING INC.**  
P.O. BOX 1800  
ROOSEVELT, UTAH 84066  
(435) 232-4321





## CROSS SECTIONS KARREN TRUST 4-30C4

WELL LOCATION: NW/NE SECTION 30, T3S, R4W, U.S.B.&M.  
DUCHESNE COUNTY, UTAH



### LEGEND

--- EXISTING CONTOURS  
— PROPOSED CONTOURS



CUT  
FILL

### ESTIMATED EARTHWORK QUANTITIES

\* NO SHRINK OR SWELL FACTORS HAVE BEEN USED  
(QUANTITIES EXPRESSED IN CUBIC YARDS)

ITEM	CUT	FILL	EXCESS/ IMPORT	6" T.S.*
PAD	1,170	1,170	0	2,420
PIT	3,890	-	0	-

\*(T.S.) = TOPSOIL STRIPPING

### CROSS SECTIONS

#### KARREN TRUST 4-30C4

WELL LOCATION: NW/NE SECTION 30, T3S, R4W, U.S.B.&M.  
DUCHESNE COUNTY, UTAH



**CROSS  
SECTIONS**

DECEMBER 24, 2014  
SCALE: 1" = 80'  
DESIGN: MA,RFII DRAWN: JMH

SHEET NO.  
**3**



**OUTLAW  
ENGINEERING INC.**  
P.O. BOX 1800  
ROOSEVELT, UTAH 84066  
(435) 232-4321





RECEIVED: February 12, 2015



## RIG LAYOUT

## KARREN TRUST 4-30C4

WELL LOCATION: NW/NE SECTION 30, T3S, R4W, U.S.B.&M.  
DUCESNE COUNTY, UTAH



## LEGEND

- EXISTING CONTOURS
- PROPOSED CONTOURS
- - - LIMITS OF DISTURBANCE
- X- EXISTING FENCE
- DIVERSION DITCH
- ⊙ WELL LOCATION

## SUMMARY

SEE CROSS SECTION SHEET FOR QUANTITIES

## RIG LAYOUT

## KARREN TRUST 4-30C4

WELL LOCATION: NW/NE SECTION 30, T3S, R4W, U.S.B.&M.  
DUCESNE COUNTY, UTAH




**RIG  
LAYOUT**

DECEMBER 24, 2014  
SCALE: 1" = 80'  
DESIGN: MA, RFII DRAWN: JMH

SHEET NO.  
**4**



**OUTLAW  
ENGINEERING INC.**  
P.O. BOX 1800  
ROOSEVELT, UTAH 84066  
(435) 232-4321









# PRODUCTION FACILITY LAYOUT

## KARREN TRUST 4-30C4

WELL LOCATION: NW/NE SECTION 30, T3S, R4W, U.S.B.&M.  
DUCHESNE COUNTY, UTAH



LEGEND	
	EXISTING CONTOURS
	PROPOSED CONTOURS
	LIMITS OF DISTURBANCE
	EXISTING FENCE
	DIVERSION DITCH
	BERM
	WELL LOCATION
	RECLAIMED AREA

### SUMMARY

APPROX UN-RECLAIMED AREA = 2.04 ACRES  
APPROX RECLAIMED AREA = 0.92 ACRES

### PRODUCTION FACILITY LAYOUT


## KARREN TRUST 4-30C4

WELL LOCATION: NW/NE SECTION 30, T3S, R4W, U.S.B.&M.  
DUCHESNE COUNTY, UTAH



**OUTLAW  
ENGINEERING INC.**

P.O. BOX 1800  
ROOSEVELT, UTAH 84066  
(435) 232-4321



**PRODUCTION  
LAYOUT**




DECEMBER 24, 2014  
SCALE: 1" = 80'  
DESIGN: MA,RFII DRAWN: JMH

SHEET NO.  
**5**

RECEIVED: February 12, 2015



**SURFACE USE AREA**  
GLEN A. KARRER FAMILY LIVING TRUST = **4.404 ACRES**, MORE OR LESS

 = FOUND SECTION CORNER  
 = SECTION LINE  
 = QUARTER SECTION LINE  
 = SIXTEENTH SECTION LINE  
 = PROPOSED RIGHT-OF-WAY

SCALE: 1" = 400'  
11X17 SHEET


REVIEWED: JLW	DRAWN: RLH
---------------	------------

EP ENERGY▲




SHEET NO.  
1 OF 1

# 5M BOP STACK and CHOKE MANIFOLD SYSTEM



10000-15000-20000 psi System








EP ENERGY

## WELL LOCATION PLAT

## WELL: KARREN TRUST 4-30C4

PAD LOCATION: NW/NE, SECTION 30, T.3S, R.4W, U.S.B.&M.  
DUCESNE COUNTY, UTAH

## CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM THE FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION, AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

## LEGEND


- = FOUND SECTION CORNER
- = CALC. SECTION CORNER
- = PROPOSED WELL HEAD

## NOTES:

1. WELL FOOTAGES ARE MEASURED AT RIGHT ANGLES TO THE SECTION LINE.
2. ALL BEARINGS AND DISTANCES ARE MEASURED UNLESS OTHERWISE NOTED.
3. BEARINGS ARE DERIVED FROM G.P.S. OBSERVATIONS AND EQUIPMENT.
4. THE GENERAL LAND OFFICE G.L.O. PLAT WAS USED FOR REFERENCE

## BASIS OF ELEVATION

SPOT ELEVATION AT THE NORTHEAST CORNER OF SECTION 30, T3S, R4W, U.S.B.&M. NAVD 88 DATUM USING THE UTAH REFERENCE NETWORK SYSTEM. SAID ELEVATION IS 5685.41 FEET.



REGISTERED LAND SURVEYOR  
REGISTRATION NO. 5047065  
STATE OF UTAH



**OUTLAW**  
ENGINEERING INC.  
P.O. BOX 1800  
ROOSEVELT, UTAH 84066  
(435) 232-4321

EP ENERGY

## WELL LOCATION PLAT

## WELL: KARREN TRUST 4-30C4

PAD LOCATION: NW/NE, SECTION 30,  
T. 3 S., R. 4 W., U.S.B.&M.  
DUCESNE COUNTY, UTAH

**NAD 83 (SURFACE LOCATION)**  
LATITUDE = 40°11'47.33919"N (40.196483)  
LONGITUDE = 110°22'34.49886"W (110.376250)  
**NAD 27 (SURFACE LOCATION)**  
LATITUDE = 40°11'47.49247"N (40.196526)  
LONGITUDE = 110°22'31.93997"W (110.375539)




DATE SURVEYED: JANUARY 5, 2015  
SURVEYED BY: CW/SY  
DRAWN: JANUARY 12, 2015  
DRAWN: JLW  
SCALE: 1" = 1000'

SHEET NO.

1

RECEIVED: February 12, 2015



**OUTLAW  
ENGINEERING INC.**

P.O. BOX 1800  
ROOSEVELT, UTAH 84066  
(435) 232-4321



PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY OUTLAW ENGINEERING, INC. AND MAY NOT REFLECT ACTUAL LOCATION OF PROPERTY LINES

### LEGEND

- Karren Trust 4-30C4 Site Location
- Proposed Access Road
- Existing Access Road

■ Federal ■ Private ■ State ■ Tribal

## KARREN TRUST 4-30C4

WELL LOCATION: NW/NE SECTION 30, T.3S, R.4W, U.S.B.&M.  
DUCHESE COUNTY, UTAH

**EP ENERGY**

USGS 7.5'  
Duchesne NE  
Quadrangle

DEC 27, 2014  
SCALE: 1" = 8,342'  
AUTHOR: BWH


SHEET  
**A**

**Site Location**

0 2,000 4,000 6,000 8,000 Feet

VERSION: **V2**  
SURVEYED: **12-17-14**





**OUTLAW  
ENGINEERING INC.**

P.O. BOX 1800  
ROOSEVELT, UTAH 84066  
(435) 232-4321



PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY OUTLAW  
ENGINEERING, INC. AND MAY NOT REFLECT ACTUAL LOCATION OF PROPERTY LINES

**Proposed Access  
Road**

0 500 1,000 1,500 2,000 Feet

VERSION: **V2**  
SURVEYED: **12-17-14**

### LEGEND

- Proposed Access Road
- Existing Access Road
- Proposed Pad

Federal
  Private
  State
  Tribal

## KARREN TRUST 4-30C4

WELL LOCATION: NW/NE SECTION 30, T.3S, R.4W, U.S.B.&M.  
DUCHESTER COUNTY, UTAH


**EP ENERGY**

USGS 7.5'  
Duchesne NE  
Quadrangle  
2014 Google Imagery

DEC 27, 2014  
SCALE: 1" = 2,000'  
AUTHOR: BWH

SHEET  
**B**





**OUTLAW  
ENGINEERING INC.**

P.O. BOX 1800  
ROOSEVELT, UTAH 84066  
(435) 232-4321



PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY OUTLAW ENGINEERING, INC. AND MAY NOT REFLECT ACTUAL LOCATION OF PROPERTY LINES

**Proposed Pipeline  
& Powerline**

0 500 1,000 1,500 2,000 Feet

VERSION: **V2**

SURVEYED: **12-17-14**

#### LEGEND

- Proposed 66' ROW
- Proposed Access Road
- Existing Access Road
- Proposed Pad

■ Federal ■ Private ■ State ■ Tribal

## KARREN TRUST 4-30C4

WELL LOCATION: NW/NE SECTION 30, T.3S, R.4W, U.S.B.&M.  
DUCHESTER COUNTY, UTAH


**EP ENERGY**

USGS 7.5'  
Duchesne NE  
Quadrangle  
2014 Google Imagery

DEC 27, 2014  
SCALE: 1" = 2,000'  
AUTHOR: BWH

SHEET  
**C**





**OUTLAW  
ENGINEERING INC.**

P.O. BOX 1800  
ROOSEVELT, UTAH 84066  
(435) 232-4321

PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY OUTLAW  
ENGINEERING, INC. AND MAY NOT REFLECT ACTUAL LOCATION OF PROPERTY LINES

**Surrounding  
Wells**

0 500 1,000 1,500 2,000 Feet

VERSION: V2  
SURVEYED: 12-17-14

#### LEGEND

- ▲ Approved Permit
- ✦ Drilling
- Producing
- ✖ Retired APD
- ◆ Plugged & Abandoned
- Shut-In
- One Mile Radius

Federal
  Private
  State
  Tribal

## KARREN TRUST 4-30C4

WELL LOCATION: NW/NE SECTION 30, T.3S, R.4W, U.S.B.&M.  
DUCHEсне COUNTY, UTAH

**EP ENERGY**

USGS 7.5'  
Duchesne NE  
Quadrangle

DEC 27, 2014  
SCALE: 1" = 2,000'  
AUTHOR: BWH

SHEET  
**D**



February 11, 2015

State of Utah Division of Oil, Gas and Mining  
Attn: Mr. Brad Hill  
1594 West North Temple, Suite 1210  
Salt Lake City, Utah 84114-5801

RE: Application for Permit to Drill  
Karren Trust 4-30C4  
SHL: 763' FNL & 1733' FEL  
NW/4NE/4 of Section 30, Township 3 South, Range 4 West  
Duchesne County, Utah

Dear Mr. Hill:

In accordance with the rules and regulations of the State of Utah, EP Energy E&P Company, L.P. ("EP Energy") is submitting an Application for Permit to Drill ("APD") for the proposed Karren Trust 4-30C4 ("Well") to the Utah Division of Oil, Gas & Mining ("UDOGM"). Concurrently with the filing of the APD for the Well, this *Application for Permit to Drill* letter hereby serves as notice to UDOGM that EP Energy is actively working to finalize the Surface Use and Right-of-Way Agreement ("Surface Agreement") with the surface owner of the Well, whose contact information is as follows ("Surface Owner"):

Glen A. Karren Family Living Trust, under agreement dated March 5, 2008  
PO Box 170  
Duchesne, UT 84021-0170  
Telephone: (435) 823-6355

EP Energy has been diligently negotiating in good-faith with the Surface Owner for several months and is nearing an agreement on the Surface Agreements for the proposed Well. Although EP Energy is confident the Surface Agreements will be executed soon, we are filing the APD without the executed Surface Agreements due to the demands of our drilling schedule. This will allow UDOGM to begin the permitting process as EP Energy finalizes the Surface Agreements. The Affidavit of Surface Agreements ("Affidavit") will be forwarded directly to your office as soon as the Surface Agreements are executed.

UDOGM's effort to begin processing the APD without the executed Surface Agreements is greatly appreciated. EP Energy fully understands the APD will not be approved until we submit the Affidavit or otherwise comply with the Surface Owner Protection Act Provision R649-3-38.

If you have any further questions, please feel free to contact me at your convenience using the phone number and/or email address below.

Very truly yours,

A handwritten signature in blue ink that reads "Jacquelyn Lynch". The signature is fluid and cursive, with the first name "Jacquelyn" being more prominent than the last name "Lynch".

Jacquelyn Lynch

EP Energy E&P Company, L.P.  
Landman  
1001 Louisiana Street, Suite 2525D  
Houston, Texas 77002  
Office: (713) 997-5747  
Jacquelyn.Lynch@EPEnergy.com



EP Energy E&P Company, L.P.

**Related Surface Information**

**1. Current Surface Use:**

- Livestock Grazing and Oil and Gas Production.

**2. Proposed Surface Disturbance:**

- The road will be crown and ditch. Water wings will be constructed on the access road as needed.
- The topsoil will be windrowed and re-spread in the borrow area.
- New road to be constructed will be approximately .69 miles in length and 66 feet wide.
- All equipment and vehicles will be confined to the access road, pad and area specified in the APD.

**3. Location Of Existing Wells:**

- Existing oil, gas wells within one (1) mile radius of proposed well are provided in EXHIBIT C.

**4. Location And Type Of Drilling Water Supply:**

- Drilling water: Duchesne City Water

**5. Existing/Proposed Facilities For Productive Well:**

- There are no existing facilities that will be utilized for this well.
- A pipeline corridor .69 miles will parallel the proposed access road. The corridor will contain one 4 inch gas line and one 2 inch gas line and one 2 inch Salt Water disposal line. Rehabilitation of unneeded, previously disturbed areas will consist of backfilling and contouring the reserve pit area; backsloping and contouring all cut and fill slopes. These areas will be reseeded. Refer to plans for reclamation of surface for details.
- Upgrade and maintain access roads and drainage control structures (e.g., culverts, drainage dips, ditching, etc.) as necessary to prevent soil erosion and accommodate safe, year-round traffic.

**6. Construction Materials:**

- Native soil from road and location will be used for construction materials along with gravel and/or scoria road base material. In the event that conditions should necessitate graveling of all or part of the access road and location, surfacing materials will be purchased from commercial suppliers in the marketing area.

**7. Methods For Handling Waste Disposal:**

- The reserve pit will be designed to prevent the collection of surface runoff and will be constructed with a minimum of ½ the total depth below the original ground surface on the lowest point with the pit. The pit will be lined with a 20-mil polyethylene to prevent leakage of fluids. The liner will be rolled into place and secured at the ends, i.e. buried on top of the pit berms. Prior to use, the reserve pit will be fenced on three sides; the fourth side will be fenced at the time the rig is removed. Drilling fluids, cuttings and produced water will be contained in the reserve pit (trash will be placed in the trash cage). Fluids in the reserve pit will be allowed to evaporate prior to pit burial.
- Garbage and other trash will be contained in the portable trash cage and hauled off the location to an authorized disposal site. Any trash on the pad will be cleaned up prior to the rig moving off location and hauled to an authorized disposal site.
- Sewage will be handled in Portable Toilets.
- Produced water will be placed in the reserve pit for a period not to exceed ninety days after initial production. Any hydrocarbons produced during completion work will be contained in test tanks and removed from the location at a later date.
- Water from the reserve pit may be used for drilling of additional wells. The water will be trucked along access roads as approved in pertinent APD's

**8. Ancillary Facilities:**

- There will be no ancillary facilities associated with this project.

9. **Surface Reclamation Plans:**

Backfilling of the pits will be done when dry. In the event of a dry hole, the location will be re-contoured, the topsoil will be distributed evenly over the entire location, and the seedbed prepared.

- Seed will be planted after September 15<sup>th</sup>, and prior to ground frost, or seed will be planted after the frost has left and before May 15<sup>th</sup>. Slopes to steep for machinery will be hand broadcast and raked with twice the specified amount of seed.
  1. The construction program and design are on the attached cut, fill and cross sectional diagrams.
  2. Prior to construction, all topsoil will be removed from the entire site and stockpiled. Topsoil for this site is the first 6 inches of soil materials.
  3. After the location has been reshaped and after redistributing the topsoil, the operator will rip and scarify the drilling platform and access road on the contour, to a depth of at least 12 inches.
- Rehabilitation will begin upon the completion of the drilling. Complete rehabilitation will depend on weather conditions and the amount of time required to dry the reserve pit.
  1. All rehabilitation work including seeding will be completed as soon as weather and the reserve pit conditions are appropriate.
  2. Landowner will be contacted for rehabilitation requirements.

10. **Surface Ownership:**

Glen A. Karren Family Living Trust, under agreement dated March 2, 2008  
PO Box 170  
Duchesne, Utah 84021-0170  
435-823-6355

**Other Information:**

- The surface soil consists of clay, and silt.
- Flora – vegetation consists of the following: Sagebrush, Juniper and prairie grasses.
- Fauna – antelope, deer, coyotes, raptors, small mammals, and domestic grazing animals.
- Current surface uses – Livestock grazing and mineral exploration and production.

• **Operator and Contact Persons:**

**Construction and Reclamation:**

EP Energy E&P Company, L.P.  
Wayne Garner  
PO Box 410  
Altamont, Utah 84001  
435-454-3394 – Office  
435-823-1490 – Cell


**Regarding This APD**

EP Energy E&P Company, L.P.  
Maria S. Gomez  
1001 Louisiana, Rm 2730D  
Houston, Texas 77002  
713-997-5038 – Office

**Drilling**

EP Energy E&P Company, L.P.  
Brad MacAfee – Drilling Engineer  
1001 Louisiana, Rm 2660D  
Houston, Texas 77002  
713-997-6383 – office  
281-813-0902 – Cell





**API Number: 4301353268**



**Well Name: Karren Trust 4-30C4**

Township: T03.0S Range: R04.0W Section: 30 Meridian: U

Operator: EP ENERGY E&P COMPANY, L.P.

Map Prepared: 2/12/2015  
Map Produced by Diana Mason

Wells Query		Units	
Status		Status	
APD - Approved Permit		ACTIVE	
DRL - Spudded (Drilling Commenced)		EXPLORATORY	
GRW - Gas Injection		GAS STORAGE	
GS - Gas Storage		NF PP OIL	
LOC - New Location		NF SECONDARY	
OPS - Operation Suspended		PI OIL	
PA - Plugged Abandoned		PP GAS	
PGW - Producing Gas Well		PP GEOTHERML	
PQW - Producing Oil Well		PP OIL	
SGW - Shut-in Gas Well		SECONDARY	
SOW - Shut-in Oil Well		TERMINATED	
TA - Temp. Abandoned			
TW - Test Well		Fields	
WDW - Water Disposal		Status	
WW - Water Injection Well		Unknown	
WSW - Water Supply Well		ABANDONED	
		ACTIVE	
		COMBINED	
		INACTIVE	
		STORAGE	
		TERMINATED	



Well Name	EP ENERGY E&P COMPANY, L.P. Karren Trust 4-30C4 430135326800			
String	Surf	I1	L1	
Casing Size(in)	9.625	7.000	5.000	
Setting Depth (TVD)	2000	8450	11600	
Previous Shoe Setting Depth (TVD)	0	2000	8450	
Max Mud Weight (ppg)	8.3	10.2	12.0	
BOPE Proposed (psi)	500	10000	10000	
Casing Internal Yield (psi)	5750	11220	13940	
Operators Max Anticipated Pressure (psi)	7238		12.0	

Calculations	Surf String	9.625	"
Max BHP (psi)	.052*Setting Depth*MW=	863	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	623	NO <input type="text" value="diverter stack"/>
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	423	YES <input type="text" value="OK"/>
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	423	NO <input type="text" value="OK"/>
Required Casing/BOPE Test Pressure=		2000	psi
*Max Pressure Allowed @ Previous Casing Shoe=		0	psi   *Assumes 1psi/ft frac gradient

Calculations	I1 String	7.000	"
Max BHP (psi)	.052*Setting Depth*MW=	4482	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	3468	YES <input type="text" value="10M BOP stack, 5M annular"/>
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	2623	YES <input type="text" value="OK"/>
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	3063	NO <input type="text" value="OK"/>
Required Casing/BOPE Test Pressure=		7854	psi
*Max Pressure Allowed @ Previous Casing Shoe=		2000	psi   *Assumes 1psi/ft frac gradient

Calculations	L1 String	5.000	"
Max BHP (psi)	.052*Setting Depth*MW=	7238	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	5846	YES <input type="text" value="10M BOP stack, 5M annular"/>
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	4686	YES <input type="text" value="OK"/>
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	6545	YES <input type="text" value=""/>
Required Casing/BOPE Test Pressure=		9758	psi
*Max Pressure Allowed @ Previous Casing Shoe=		8450	psi   *Assumes 1psi/ft frac gradient

Calculations	String		"
Max BHP (psi)	.052*Setting Depth*MW=		
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=		NO <input type="text" value=""/>
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=		NO <input type="text" value=""/>
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=		NO <input type="text" value=""/>
Required Casing/BOPE Test Pressure=			psi
*Max Pressure Allowed @ Previous Casing Shoe=			psi   *Assumes 1psi/ft frac gradient

**EP ENERGY E&P COMPANY, L.P.**  
**Karren Trust 4-30C4**  
**43013532680000**

stop rot. head

Formation Depth (MD)  
 DSHNRVR 0

BMSW 1000

9.625 " Casing

2000 ' MD

2000 ' TVD

Surface ' TOC

1477 ' Tail

10 % Washout

12.25 " Hole

GRRV 3673

GRTN1 4361

MHGNY 5228

LWR GR 6521

stop cut

7 " Casing

8450 ' MD

8450 ' TVD

Surface ' TOC

6008 ' Tail

5.8 % Washout

8.75 " Hole

WSTCH 8381

TOL

8250 ' MD

8250 ' TVD

5 " Liner

11600 ' MD

11600 ' TVD

TOL ' TOC

11600 ' Tail

15 % Washout

6.125 " Hole

Blue Bench 1-13CS SWD  
 216 mi NNW 4106'- 7528'



**EP ENERGY E&P COMPANY, L.P.**  
**Karren Trust 4-30C4**  
**43013532680000**


9.625 " Casing																							
1.12511.8																							
MASP	176	Collapse Strength (psi)	3090	Collapse Load (psi)	416	Collapse DF	7.44	Burst Strength (psi)	5750	Burst Load (psi)	2000	Burst DF	2.88	Tension Strength (kips)	737	Tension DF	9.21	Neutral Point (ft)	1878	Tension Air (kips)	80.0	Tension Buoyed (kips)	75.2
MW (ppg)	4.0	Internal Grad. (psi)	0.12	Backup Mud (ppg)		Internal Mud (ppg)		Max Shoe Pressure (psi)*	3058	CSG Wt (lbs/ft)	40.0	CSG Grade	N-80	CSG Collar	LTC	Cement Lead (sx)	412	Lead Yield	2.36	Cement Tail (sx)	195	Tail Yield	1.30
7 " Casing																							
MASP	2618	Collapse Strength (psi)	9200	Collapse Load (psi)	4477	Collapse DF	2.05	Burst Strength (psi)	11220	Burst Load (psi)	6538	Burst DF	1.72	Tension Strength (kips)	797	Tension DF	3.85	Neutral Point (ft)	7132	Tension Air (kips)	245.1	Tension Buoyed (kips)	207.2
MW (ppg)	10.2	Internal Grad. (psi)	0.22	Backup Mud (ppg)		Internal Mud (ppg)		Max Shoe Pressure (psi)*	6538	CSG Wt (lbs/ft)	29.0	CSG Grade	HCP-110	CSG Collar	LTC	Cement Lead (sx)	590	Lead Yield	1.91	Cement Tail (sx)	298	Tail Yield	1.64
5 " Liner																							
MASP	4679	Collapse Strength (psi)	13418	Collapse Load (psi)	7231	Collapse DF	1.86	Burst Strength (psi)	13940	Burst Load (psi)	7231	Burst DF	1.93	Tension Strength (kips)	495	Tension DF	10.04	Neutral Point (ft)	10985	Tension Air (kips)	60.3	Tension Buoyed (kips)	49.3
MW (ppg)	12.0	Internal Grad. (psi)	0.22	Backup Mud (ppg)		Internal Mud (ppg)		Max Shoe Pressure (psi)*	8250	CSG Wt (lbs/ft)	18.0	CSG Grade	HCP-110	CSG Collar	LTC	Cement Lead (sx)	199	Lead Yield	1.52	Cement Tail (sx)		Tail Yield	

**AFFIDAVIT OF DAMAGE SETTLEMENT AND RELEASE**

Jacquelyn L. Lynch personally appeared before me, and, being duly sworn, deposes and says:

1. My name is Jacquelyn L. Lynch. I am a Landman for EP Energy E&P Company, L.P., whose address is 1001 Louisiana St., Houston, Texas 77002 ("EP Energy").
2. EP Energy is the operator of the proposed Karren Trust 4-30C4 well (the "Well") to be located in the NW/4NW/4 of Section 30, Township 3 South, Range 4 West, USM, Duchesne County, Utah (the "Drillsite Location"). The surface owner of the Drillsite Location is Glenn A. Karren Family Living Trust whose address is PO Box 170, Duchesne, Utah 84021 (the "Surface Owner"). The Surface Owner's telephone number is (435) 454-4245.
3. EP Energy and the Surface Owner have entered into a Surface Use Agreement dated February 16, 2015 to cover any and all injuries or damages of every character and description sustained by the Surface Owner or Surface Owner's property as a result of operations associated with the drilling of the Well.

FURTHER AFFIANT SAYETH NOT.

  
Jacquelyn L. Lynch

**ACKNOWLEDGMENT**

STATE OF TEXAS           §  
                                     §  
COUNTY OF HARRIS     §

Sworn to and subscribed before me on this 12th day of March, 2015, by Jacquelyn L. Lynch, as Landman for EP Energy E&P Company, L.P., a Delaware limited partnership.

  
NOTARY PUBLIC

My Commission Expires:

8/2/2018



# **ON-SITE PREDRILL EVALUATION**

## **Utah Division of Oil, Gas and Mining**

**Operator** EP ENERGY E&P COMPANY, L.P.  
**Well Name** Karren Trust 4-30C4  
**API Number** 43013532680000      **APD No** 11071      **Field/Unit** ALTAMONT  
**Location:** 1/4,1/4 NWNE      **Sec** 30      **Tw** 3.0S      **Rng** 4.0W      763 FNL 1733 FEL  
**GPS Coord (UTM)** 553088 4449755      **Surface Owner** Glen A. Karren Family Living Trust

### **Participants**

Glen Karren (surface owner); Kelsey Carter (EP Energy permitting); Randy Fredrick (EP Energy Construction); Jay Van tassel (EP Lands); Dennis Ingram (DOGM)

### **Regional/Local Setting & Topography**

The Karren Trust 4-30C4 well is proposed in northeastern Utah and can be accessed by turning north off U.S. Highway 40 onto Highway 87 for 3.2 miles where an existing access road will be upgraded to the east for 0.4 miles and the new road will lead southeast into the well site. This well is located along the eastern side of bench property that drops into a large southeast drainage that continues past Rocky Point into the Duchesne Flood Plain east of that town some 1.20 miles away. The Airport has an east/west existing runway less than a quarter mile to the south, and a north/south runway just over a quarter mile to the west. The immediate surface is nearly flat and shows less than a two-foot drop in elevation across the width of the pad.

### **Surface Use Plan**

#### **Current Surface Use**

Recreational  
Wildlfe Habitat

#### **New Road Miles**

0.69

#### **Well Pad**

**Width** 282      **Length** 410

#### **Src Const Material**

Onsite

#### **Surface Formation**

UNTA

#### **Ancillary Facilities** N

Reserve pit and disturbance area is 417' wide by 460' long

### **Waste Management Plan Adequate?**

### **Environmental Parameters**

#### **Affected Floodplains and/or Wetlands** N

#### **Flora / Fauna**

Pinion/juniper, sagebrush, prickly pear cactus, bunch grass;

Elk, mule deer, mountain lion, bobcat, coyote, fox, jack and cottontail rabbits, other smaller mammals and birds typical of region.

#### **Soil Type and Characteristics**

Reddish to light brown in color, fine-grained, sandy loam with some clays and cobbles present

#### **Erosion Issues** N

**Sedimentation Issues** N**Site Stability Issues** Y

Shorten reserve pit from 150' to 140' in width and add volume to length if necessary

**Drainage Diversion Required?** N**Berm Required?** Y

tanks and location

**Erosion Sedimentation Control Required?** N**Paleo Survey Run?** N   **Paleo Potential Observed?** N   **Cultural Survey Run?** N   **Cultural Resources?** N**Reserve Pit****Site-Specific Factors****Site Ranking**

<b>Distance to Groundwater (feet)</b>	>200	0
<b>Distance to Surface Water (feet)</b>	300 to 1000	2
<b>Dist. Nearest Municipal Well (ft)</b>	1320 to 5280	5
<b>Distance to Other Wells (feet)</b>	>1320	0
<b>Native Soil Type</b>	High permeability	20
<b>Fluid Type</b>	Fresh Water	5
<b>Drill Cuttings</b>	Normal Rock	0
<b>Annual Precipitation (inches)</b>		0
<b>Affected Populations</b>	10 to 30	10 to 30
<b>Presence Nearby Utility Conduits</b>	Present	15
<b>Final Score</b>		53   1 Sensitivity Level

**Characteristics / Requirements**

Proposed reserve pit off the north side in 0.1 feet of fill at corner number "C", measuring 100' wide by 150' long by 8' deep. Reserve pit will be shortened from 110' to 100' to stabilize cobble rock hillside to the north and reduce fill area.

**Closed Loop Mud Required?**   **Liner Required?** Y   **Liner Thickness** 20   **Pit Underlayment Required?** Y**Other Observations / Comments**

Shorten pit width from 110' to 100' or less to prevent any potential seepage from adjacent, cobble rock hillside and reduce fill area on pit berm. Production tanks on the southwest side of location. This well was staked as close to airport runway as is allowed.

Dennis Ingram  
Evaluator

2/26/2015  
Date / Time

# Application for Permit to Drill

## Statement of Basis

### Utah Division of Oil, Gas and Mining

APD No	API WellNo	Status	Well Type	Surf Owner	CBM
11071	43013532680000	LOCKED	OW	P	No
Operator	EP ENERGY E&P COMPANY, L.P.		Surface Owner-APD	Glen A. Karren Family Living Trust	
Well Name	Karren Trust 4-30C4		Unit		
Field	ALTAMONT		Type of Work	DRILL	
Location	NWNE 30 3S 4W U 763 FNL (UTM) 553093E 4449745N		1733 FEL GPS Coord		

#### Geologic Statement of Basis

EP proposes to set 40 feet of conductor and 2,000 feet of surface casing both of which will be cemented to surface. The surface hole will be drilled utilizing air/fresh water mud. The estimated depth to the base of moderately saline ground water is 1,000 feet. A search of Division of Water Rights records indicates that there are 23 water wells within a 10,000 foot radius of the center of Section 30. These wells probably produce water from the Duchesne River Formation and associated alluvium. Depths of the wells fall in the range of 29-500 feet. Depth is not listed for one well. The wells are listed as being used for irrigation, stock watering, municipal and domestic. The proposed drilling, casing and cement program should adequately protect the highly used Duchesne River aquifer.

Brad Hill  
APD Evaluator

3/3/2015  
Date / Time

#### Surface Statement of Basis

There aren't any drainage issues crossing the proposed well pad; however, a large, deep drainage is located immediately north of the well pad and drains southeasterly into the Duchesne River Corridor. The production facility is proposed along the south side of the location, and the operator shall berm both the tanks and the location to prevent fluids from leaving location.

A reserve pit is planned for the north side of location between corners #5 & #7 and has a large downhill slope into the adjacent canyon. Furthermore, cobble rocks litter the ground as the topography turns downward to the north. Therefore the operator shall shorten the width of the proposed pit from 110' to 100' or less to stabilize the north side. Some of the pit spoils shall also be piled to the north but not beyond the disturbance line where it will run down slope. The length of this pit can be extended by ten feet to make up for the loss along the north side. The underlying ground shows round cobbles, sandstone and some clays, and therefore the operator shall install a felt pad underlayment before installing a 20 mil synthetic liner to prevent leaks or seepage of the drilling fluids.

A presite was scheduled and performed on February 26, 2015 to take input and address issues regarding the permitting of the Karren Trust 4-30C4 well. Glen Karren was shown as the landowner of record and was therefore invited to participate. EP Energy was still working with the landowner to gain a surface damage or landowner agreement, and this permit should not be released until the State has received proof of that document.



Dennis Ingram  
Onsite Evaluator

2/26/2015  
Date / Time

**Conditions of Approval / Application for Permit to Drill**

Category	Condition
Pits	A synthetic liner with a minimum thickness of 20 mils with a felt subliner shall be properly installed and maintained in the reserve pit. This pit shall also be fenced to prevent deer and wildlife from entering same.
Pits	The reserve pit should be located on the north side of the location. Also shorten width from 110' to 100' or less
Surface	The well site shall be bermed to prevent fluids from entering or leaving the pad.

CONFIDENTIAL

## WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 2/12/2015

API NO. ASSIGNED: 43013532680000

WELL NAME: Karren Trust 4-30C4

OPERATOR: EP ENERGY E&amp;P COMPANY, L.P. (N3850)

PHONE NUMBER: 713 997-5038

CONTACT: Maria S. Gomez

PROPOSED LOCATION: NWNE 30 030S 040W

Permit Tech Review: ☒

SURFACE: 0763 FNL 1733 FEL

Engineering Review: ☒

BOTTOM: 0763 FNL 1733 FEL

Geology Review: ☒

COUNTY: DUCHESNE

LATITUDE: 40.19642

LONGITUDE: -110.37622

UTM SURF EASTINGS: 553093.00

NORTHINGS: 4449745.00

FIELD NAME: ALTAMONT

LEASE TYPE: 4 - Fee

LEASE NUMBER: Fee

PROPOSED PRODUCING FORMATION(S): GREEN RIVER(LWR)-WASATCH

SURFACE OWNER: 4 - Fee

COALBED METHANE: NO

## RECEIVED AND/OR REVIEWED:

☒ PLAT☒ Bond: STATE/FEE - 400JU0708☐ Potash☐ Oil Shale 190-5☐ Oil Shale 190-3☐ Oil Shale 190-13☒ Water Permit: Duchesne City☐ RDCC Review:☒ Fee Surface Agreement☐ Intent to Commingle

Commingling Approved

## LOCATION AND SITING:

☐ R649-2-3.

Unit:

☐ R649-3-2. General☐ R649-3-3. Exception☒ Drilling Unit

Board Cause No: Cause 139-124

Effective Date: 11/6/2014

Siting: 8 WELLS PER SECTION

☐ R649-3-11. Directional Drill

Comments: Presite Completed

Stipulations: 5 - Statement of Basis - bhill  
7 - BOPE Test - daynedoucet  
12 - Cement Volume (3) - ddoucet  
25 - Surface Casing - ddoucet

RECEIVED: March 12, 2015



GARY R. HERBERT  
*Governor*

SPENCER J. COX  
*Lieutenant Governor*

# State of Utah

## DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
*Executive Director*

### Division of Oil, Gas and Mining

JOHN R. BAZA  
*Division Director*

## Permit To Drill

\*\*\*\*\*

**Well Name:** Karren Trust 4-30C4

**API Well Number:** 43013532680000

**Lease Number:** Fee

**Surface Owner:** FEE (PRIVATE)

**Approval Date:** 3/12/2015

### Issued to:

EP ENERGY E&P COMPANY, L.P., 1001 Louisiana, Houston, TX 77002

### Authority:

Pursuant to Utah Code Ann. 40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 139-124. The expected producing formation or pool is the GREEN RIVER(LWR)-WASATCH Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

### Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

### General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

### Conditions of Approval:

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

Cement volume for the 7 inch casing shall be determined from actual hole diameter in order to place tail cement from the pipe setting depth back to 6000' MD and lead cement back to surface as indicated in the submitted drilling plan.

A properly lubricated rotating head shall be used while air drilling.

Surface casing shall be cemented to the surface.

### Additional Approvals:

The operator is required to obtain approval from the Division of Oil, Gas and mining before performing any of the following actions during the drilling of this well:

- Any changes to the approved drilling plan - contact Dustin Doucet
- Significant plug back of the well - contact Dustin Doucet
- Plug and abandonment of the well - contact Dustin Doucet

### **Notification Requirements:**

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well - contact Carol Daniels  
OR  
submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website  
at <http://oilgas.ogm.utah.gov>
- 24 hours prior to testing blowout prevention equipment - contact Dan Jarvis
- 24 hours prior to cementing or testing casing - contact Dan Jarvis
- Within 24 hours of making any emergency changes to the approved drilling program  
- contact Dustin Doucet
- 24 hours prior to commencing operations to plug and abandon the well - contact Dan Jarvis

### **Contact Information:**

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voicemail message if the person is not available to take the call):

- Carol Daniels 801-538-5284 - office
- Dustin Doucet 801-538-5281 - office  
801-733-0983 - after office hours
- Dan Jarvis 801-538-5338 - office  
801-231-8956 - after office hours

### **Reporting Requirements:**

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) - due within 5 days of spudding the well
- Monthly Status Report (Form 9) - due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) - due prior to implementation
- Written Notice of Emergency Changes (Form 9) - due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) - due prior to implementation
- Report of Water Encountered (Form 7) - due within 30 days after completion
- Well Completion Report (Form 8) - due within 30 days after completion or plugging

Approved By:

**Approved By:**

A handwritten signature in black ink, appearing to read "J. Rogers", written over a light blue horizontal line.

For John Rogers  
Associate Director, Oil & Gas

CONFIDENTIAL

Carol Daniels <caroldaniels@utah.gov>

NWNE SEC 30 T03S R04W

FEE LEASE

## 24 hour notice running casing & cementing

1 message

LANDRIG009 (Precision 406) <LANDRIG009@epenergy.com>

Fri, Mar 27, 2015 at 6:40 AM

To: "alexishuefner@utah.gov" <alexishuefner@utah.gov>, "MacAfee, Bradley D" <Brad.MacAfee@epenergy.com>, "caroldaniels@utah.gov" <caroldaniels@utah.gov>, "dennisingram@utah.gov" <dennisingram@utah.gov>, "Dodd, Robert W" <Robert.Dodd@epenergy.com>, "Mangum, Danny R (Contractor)" <danny.mangum@epenergy.com>, "Gomez, Maria S" <Maria.Gomez@epenergy.com>, "Derden, Roy Lynn (Contractor)" <Roy.Derden@epenergy.com>

RE: EP ENERGY

KAREN TRUST 4-30C4

API # 43013532680000

ALTAMONT FIELD

DUCHESNE COUNTY

Leon Ross Drilling moved in and commenced drilling the 12¼" surface hole @ 7:30 pm on 3/825/2015. We plan on running and cementing 9-5/8" Surface Casing to +/- 2,120' within 24hrs.

Thanks,

Lloyd Rowell / Morgan Harden

EP Energy / PD 406

713-997-1220 (Rig)

435-823-1764 (Cell)

THIS E-MAIL AND ANY MATERIALS TRANSMITTED WITH IT MAY CONTAIN CONFIDENTIAL OR PROPRIETARY MATERIAL FOR THE SOLE USE OF THE INTENDED RECIPIENT. ANY REVIEW, USE, DISTRIBUTION OR DISCLOSURE BY OTHERS IS STRICTLY PROHIBITED. IF YOU ARE NOT THE INTENDED RECIPIENT, OR AUTHORIZED TO RECEIVE THE INFORMATION FROM THE RECIPIENT, PLEASE NOTIFY THE SENDER BY REPLY E-MAIL AND DELETE ALL COPIES OF THIS MESSAGE.

Alexis Huefner <alexishuefner@utah.gov>

---

**24 HR SPUD NOTICE 20" CASING.**

1 message

---

**LANDRIG009 (Precision 406)** <LANDRIG009@epenergy.com>

Tue, Mar 24, 2015 at 7:40 AM

To: "alexishuefner@utah.gov" <alexishuefner@utah.gov>, "MacAfee, Bradley D" <Brad.MacAfee@epenergy.com>, "caroldaniels@utah.gov" <caroldaniels@utah.gov>, "dennisingram@utah.gov" <dennisingram@utah.gov>, "Dodd, Robert W" <Robert.Dodd@epenergy.com>, "Mangum, Danny R (Contractor)" <danny.mangum@epenergy.com>, "Gomez, Maria S" <Maria.Gomez@epenergy.com>, "Derden, Roy Lynn (Contractor)" <Roy.Derden@epenergy.com>

RE: EP ENERGY

KAREN TRUST 4-30C4

API # 43013532680000

ALTAMONT FIELD

DUCHESNE COUNTY

763 FWL 1733 FEL

NWNE 30 3S 4W

**CONFIDENTIAL**

Leon Ross Drilling spudded the well @ 10:00hrs on 3/24/2015. We plan on running and cementing 20" Conductor Casing to +/- 40' within 24hrs.

Thanks,

Lloyd Rowell / Morgan Harden

EP Energy / PD 406

713-997-1220 (Rig)

435-823-1764 (Cell)

---

THIS E-MAIL AND ANY MATERIALS TRANSMITTED WITH IT MAY CONTAIN CONFIDENTIAL OR PROPRIETARY MATERIAL FOR THE SOLE USE OF THE INTENDED RECIPIENT. ANY REVIEW, USE, DISTRIBUTION OR DISCLOSURE BY OTHERS IS STRICTLY PROHIBITED. IF YOU ARE NOT THE INTENDED RECIPIENT, OR AUTHORIZED TO RECEIVE THE INFORMATION FROM THE RECIPIENT, PLEASE NOTIFY THE SENDER BY REPLY E-MAIL AND DELETE ALL COPIES OF THIS MESSAGE.

CONFIDENTIAL

Carol Daniels <caroldaniels@utah.gov>

NWNE SEC 30 T03S R04W FEE LEASE

**24 HR NOTICE RUNNING CASING/ CEMENTING.**

1 message

LANDRIG009 (Precision 406) <LANDRIG009@epenergy.com>

Sun, Apr 19, 2015 at 4:01 AM

To: "alexishuefner@utah.gov" <alexishuefner@utah.gov>, "MacAfee, Bradley D" <Brad.MacAfee@epenergy.com>, "caroldaniels@utah.gov" <caroldaniels@utah.gov>, "dennisingram@utah.gov" <dennisingram@utah.gov>, "Dodd, Robert W" <Robert.Dodd@epenergy.com>, "Mangum, Danny R (Contractor)" <danny.mangum@epenergy.com>, "Gomez, Maria S" <Maria.Gomez@epenergy.com>, "Derden, Roy Lynn (Contractor)" <Roy.Derden@epenergy.com>

RE: EP ENERGY

~~KAREN~~  
KAREN TRUST 4-30C4

API # 43013532680000

ALTAMONT FIELD

DUCHESNE COUNTY

We plan on running and cementing 7" 29# P-110HC LT&C Intermediate Casing to +/- 8,453' within 24hrs

Thanks,

Lloyd Rowell / Morgan Harden

EP Energy / PD 406

713-997-1220 (Rig)

435-823-1764 (Cell)

THIS E-MAIL AND ANY MATERIALS TRANSMITTED WITH IT MAY CONTAIN CONFIDENTIAL OR PROPRIETARY MATERIAL FOR THE SOLE USE OF THE INTENDED RECIPIENT. ANY REVIEW, USE, DISTRIBUTION OR DISCLOSURE BY OTHERS IS STRICTLY PROHIBITED. IF YOU ARE NOT THE INTENDED RECIPIENT, OR AUTHORIZED TO RECEIVE THE INFORMATION FROM THE RECIPIENT, PLEASE NOTIFY THE SENDER BY REPLY E-MAIL AND DELETE ALL COPIES OF THIS MESSAGE.



CONFIDENTIAL

Carol Daniels <caroldaniels@utah.gov>

NWNE S-30 T03S R04W FEE LEASE

## 24hr Notice Run & Cement Casing

1 message

LANDRIG009 (Precision 406) <LANDRIG009@epenergy.com>

Thu, Apr 23, 2015 at 5:24 AM

To: "alexishuefner@utah.gov" <alexishuefner@utah.gov>, "MacAfee, Bradley D" <Brad.MacAfee@epenergy.com>, "caroldaniels@utah.gov" <caroldaniels@utah.gov>, "dennisingram@utah.gov" <dennisingram@utah.gov>, "Dodd, Robert W" <Robert.Dodd@epenergy.com>, "Mangum, Danny R (Contractor)" <danny.mangum@epenergy.com>, "Gomez, Maria S" <Maria.Gomez@epenergy.com>, "Derden, Roy Lynn (Contractor)" <Roy.Derden@epenergy.com>

RE: EP ENERGY

*KAREN*  
KAREN TRUST 4-30C4

API # 43013532680000

ALTAMONT FIELD

DUCHESNE COUNTY

We plan on running and cementing 5" 18# P-110HC STL Production liner to +/- 11,103' within 24hrs.

Thanks,

Lloyd Rowell / Morgan Harden

EP Energy / PD 406

713-997-1220 (Rig)

435-823-1764 (Cell)

THIS E-MAIL AND ANY MATERIALS TRANSMITTED WITH IT MAY CONTAIN CONFIDENTIAL OR PROPRIETARY MATERIAL FOR THE SOLE USE OF THE INTENDED RECIPIENT. ANY REVIEW, USE, DISTRIBUTION OR DISCLOSURE BY OTHERS IS STRICTLY PROHIBITED. IF YOU ARE NOT THE INTENDED RECIPIENT, OR AUTHORIZED TO RECEIVE THE INFORMATION FROM THE RECIPIENT, PLEASE NOTIFY THE SENDER BY REPLY E-MAIL AND DELETE ALL COPIES OF THIS MESSAGE.

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> Fee
		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>1. TYPE OF WELL</b> Oil Well	<b>8. WELL NAME and NUMBER:</b> Karren Trust 4-30C4	
<b>2. NAME OF OPERATOR:</b> EP ENERGY E&P COMPANY, L.P.		<b>9. API NUMBER:</b> 43013532680000
<b>3. ADDRESS OF OPERATOR:</b> 1001 Louisiana , Houston, TX, 77002	<b>PHONE NUMBER:</b> 713 997-5038 Ext	<b>9. FIELD and POOL or WILDCAT:</b> ALTAMONT
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0763 FNL 1733 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWNE Section: 30 Township: 03.0S Range: 04.0W Meridian: U		<b>COUNTY:</b> DUCHESNE
		<b>STATE:</b> UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: <b>5/11/2015</b>	<input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION  OTHER: <input type="text" value="Initial Completion"/>
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:			
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:			
<input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

EP is completing into the Wasatch. Please see attached for details.

**Approved by the**  
**May 27, 2015**  
**Oil, Gas and Mining**

Date: \_\_\_\_\_

By: Derek Duff

<b>NAME (PLEASE PRINT)</b> Maria S. Gomez	<b>PHONE NUMBER</b> 713 997-5038	<b>TITLE</b> Principal Regulatory Analyst
<b>SIGNATURE</b> N/A		<b>DATE</b> 5/13/2015

**Karren Trust 4-30C4****Initial Completion****API # : 43013532680000**

**The following precautions will be taken until the RCA for the Conover is completed:**

1. Review torque turning and running of the 7" and 5" liner of anomalies.
2. Test and chart casing for 30 minutes, noting pressure if any on surface casing.
3. Test all lubricators, valves and BOP's to working pressure.
4. A frac tree with BOP equipment will be utilized during the stimulation treatment.
5. Monitor the surface casing during frac:
  - a. Lay a flowline to the flow back tank and keep the valve open.
  - b. This line will remain in place until a wire line set retrievable packer is in place isolating the casing after the frac.
6. 2 7/8" tubing will be run to isolate the casing during the flow back of the well.
7. Well pressure and annulus pressure would be monitored during this time until the well is ready for pump.

**Completion Information (Wasatch Formation)**

<b>Stage #1</b>	RU WL unit with 10K lubricator and test to 10,000 psi with glycol. Perforations from ~10603' – 10946' with ~5000 gallons of 15% HCL acid, ~3000 # of 100 mesh sand and ~150000 # of TLC 30/50. Total clean water volume is 3647 bbls.
<b>Stage #2</b>	RU WL unit with 10K lubricator and test to 10,000 psi with glycol. Perforations from ~10211' – 10521' with ~5000 gallons of 15% HCL acid, ~3000 # of 100 mesh sand and ~150000 # of TLC 30/50. Total clean water volume is 3640 bbls.
<b>Stage #3</b>	RU WL unit with 10K lubricator and test to 10,000 psi with glycol. Perforations from ~9876' – 10184' with ~5000 gallons of 15% HCL acid, ~3000 # of 100 mesh sand and ~150000 # of TLC 30/50. Total clean water volume is 3634 bbls.
<b>Stage #4</b>	RU WL unit with 10K lubricator and test to 10,000 psi with glycol. Perforations from ~9613' – 9846' with ~5000 gallons of 15% HCL acid, ~3000 # of 100 mesh sand and ~150000 # of TLC 30/50. Total clean water volume is 3630 bbls.
<b>Stage #5</b>	RU WL unit with 10K lubricator and test to 10,000 psi with glycol. Perforations from ~9337' – 9581' with ~5000 gallons of 15% HCL acid, ~3000 # of 100 mesh sand and ~150000 # of TLC 30/50. Total clean water volume is 3625 bbls.

**Stage #6** RU WL unit with 10K lubricator and test to 10,000 psi with glycol. Perforations from ~9087' – 9307' with ~5000 gallons of 15% HCL acid, ~3000 # of 100 mesh sand and ~150000 # of TLC 30/50. Total clean water volume is 3620 bbls.

**Stage #7** RU WL unit with 10K lubricator and test to 10,000 psi with glycol. Perforations from ~8797' – 9050' with ~5000 gallons of 15% HCL acid, ~3000 # of 100 mesh sand and ~150000 # of White 30/50. Total clean water volume is 3615 bbls.

**Stage #8** RU WL unit with 10K lubricator and test to 10,000 psi with glycol. Perforations from ~8521' – 8760' with ~5000 gallons of 15% HCL acid, ~3000 # of 100 mesh sand and ~150000 # of White 30/50. Total clean water volume is 3610 bbls.

### Stimulation Summary

	Top Perf	Btm. Perf	Gross Interval	Plug Depth	Net Perf Length	Total Shots	Perf Intervals	Type of Prop	Lbs of Prop	Lbs/ft	Lbs of 100 Mesh	Gals of HCL (15%)	BBLs of Clean H2O	BBLs of Slurry
Stage #1	10,603	10,946	343	NA	23	69	17	TLC 30/50	150,000	437	3,000	5,000	3,647	4,048
Stage #2	10,211	10,521	310	10,536	23	69	17	TLC 30/50	150,000	484	3,000	5,000	3,640	4,041
Stage #3	9,876	10,184	308	10,199	23	69	17	TLC 30/50	150,000	487	3,000	5,000	3,634	4,035
Stage #4	9,613	9,846	233	9,861	23	69	17	TLC 30/50	150,000	644	3,000	5,000	3,630	4,030
Stage #5	9,337	9,581	244	9,596	21	63	17	TLC 30/50	150,000	615	3,000	5,000	3,625	4,025
Stage #6	9,087	9,307	220	9,322	22	66	17	TLC 30/50	150,000	682	3,000	5,000	3,620	4,021
Stage #7	8,797	9,050	253	9,065	23	69	17	White 30/50	150,000	593	3,000	5,000	3,615	4,027
Stage #8	8,521	8,760	239	8,775	23	69	17	White 30/50	150,000	628	3,000	5,000	3,610	4,022
<b>Average per Stage</b>			<b>269</b>		<b>23</b>	<b>68</b>	<b>17</b>		<b>150,000</b>	<b>571</b>	<b>3,000</b>	<b>5,000</b>	<b>3,628</b>	<b>4,031</b>
<b>Totals per Well</b>			<b>2,150</b>		<b>181</b>	<b>543</b>	<b>136</b>		<b>1,200,000</b>		<b>24,000</b>	<b>40,000</b>	<b>29,021</b>	<b>32,250</b>




**Pre-Completion Wellbore Schematic**

Well Name: **Karren Trust 4-30C4**  
Company Name: **EP Energy**  
Field, County, State: **Altamont, Duchesne, Utah**  
Surface Location: **Lat: 40°11'47.49247" N Long: 110°22'31.93997" W**  
Producing Zone(s): **Wasatch**

Last Updated: **4/27/2015**  
By: **David Gregory**  
TD: **11,101**  
API: **43013532680000**  
AFE: **163172**

8.43 ppg KCL substitute (Clay Webb Water)  
water in the wellbore






### Post-Completion Wellbore Schematic

Well Name: **Karren Trust 4-30C4**  
 Company Name: **EP Energy**  
 Field, County, State: **Altamont, Duchesne, Utah**  
 Surface Location: **Lat: 40°11'47.49247" N Long: 110°22'31.93997" W**  
 Producing Zone(s): **Wasatch**

Last Updated: **4/27/2015**  
 By: **David Gregory**  
 TD: **11,101**  
 API: **43013532680000**  
 AFE: **163172**

8.43 ppg KCL substitute (Clay Webb Water)  
 water in the wellbore



STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MININGAMENDED REPORT ☐ FORM 8  
(highlight changes)

<b>WELL COMPLETION OR RECOMPLETION REPORT AND LOG</b>						5. LEASE DESIGNATION AND SERIAL NUMBER:				
						6. IF INDIAN, ALLOTTEE OR TRIBE NAME				
						7. UNIT or CA AGREEMENT NAME				
						8. WELL NAME and NUMBER:				
1a. TYPE OF WELL: OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> DRY <input type="checkbox"/> OTHER _____						9. API NUMBER:				
b. TYPE OF WORK: NEW WELL <input type="checkbox"/> HORIZ. LATS. <input type="checkbox"/> DEEP-EN <input type="checkbox"/> RE-ENTRY <input type="checkbox"/> DIFF. RESVR. <input type="checkbox"/> OTHER _____						10 FIELD AND POOL, OR WILDCAT				
2. NAME OF OPERATOR:						11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:				
3. ADDRESS OF OPERATOR: CITY _____ STATE _____ ZIP _____						PHONE NUMBER: _____		12. COUNTY		13. STATE <b>UTAH</b>
4. LOCATION OF WELL (FOOTAGES) AT SURFACE:  AT TOP PRODUCING INTERVAL REPORTED BELOW:  AT TOTAL DEPTH:						17. ELEVATIONS (DF, RKB, RT, GL):				
14. DATE SPUDDED:		15. DATE T.D. REACHED:		16. DATE COMPLETED: ABANDONED <input type="checkbox"/> READY TO PRODUCE <input type="checkbox"/>						
18. TOTAL DEPTH: MD _____ TVD _____		19. PLUG BACK T.D.: MD _____ TVD _____		20. IF MULTIPLE COMPLETIONS, HOW MANY? *		21. DEPTH BRIDGE MD _____ PLUG SET: TVD _____				
22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each)						23. WAS WELL CORED? NO <input type="checkbox"/> YES <input type="checkbox"/> (Submit analysis) WAS DST RUN? NO <input type="checkbox"/> YES <input type="checkbox"/> (Submit report) DIRECTIONAL SURVEY? NO <input type="checkbox"/> YES <input type="checkbox"/> (Submit copy)				
<b>24. CASING AND LINER RECORD (Report all strings set in well)</b>										
HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED	
<b>25. TUBING RECORD</b>										
SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)		
<b>26. PRODUCING INTERVALS</b>					<b>27. PERFORATION RECORD</b>					
FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS		
(A)								Open <input type="checkbox"/>	Squeezed <input type="checkbox"/>	
(B)								Open <input type="checkbox"/>	Squeezed <input type="checkbox"/>	
(C)								Open <input type="checkbox"/>	Squeezed <input type="checkbox"/>	
(D)								Open <input type="checkbox"/>	Squeezed <input type="checkbox"/>	
<b>28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC. See attached for further information on #27 &amp; #28.</b>										
DEPTH INTERVAL		AMOUNT AND TYPE OF MATERIAL								
29. ENCLOSED ATTACHMENTS: All logs are submitted to UDOGM by vendor.								30. WELL STATUS:		
<input type="checkbox"/> ELECTRICAL/MECHANICAL LOGS				<input type="checkbox"/> GEOLOGIC REPORT		<input type="checkbox"/> DST REPORT		<input type="checkbox"/> DIRECTIONAL SURVEY		
<input type="checkbox"/> SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION				<input type="checkbox"/> CORE ANALYSIS		<input type="checkbox"/> OTHER: _____				

**31. INITIAL PRODUCTION****INTERVAL A (As shown in item #26)**

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

**INTERVAL B (As shown in item #26)**

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

**INTERVAL C (As shown in item #26)**

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

**INTERVAL D (As shown in item #26)**

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

**32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)****33. SUMMARY OF POROUS ZONES (Include Aquifers):**

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

**34. FORMATION (Log) MARKERS:**

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)

**35. ADDITIONAL REMARKS (Include plugging procedure)**

**36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.**

NAME (PLEASE PRINT) \_\_\_\_\_ TITLE \_\_\_\_\_

SIGNATURE \_\_\_\_\_ DATE \_\_\_\_\_

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

\* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

\*\* ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Box 145801  
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940



**Attachment to Well Completion Report****Form 8 Dated June 14, 2015****Well Name: Karren Trust 4-30C4****Items #27 and #28 Continued****27. Perforation Record**

<b>Interval (Top/Bottom – MD)</b>	<b>Size</b>	<b>No. of Holes</b>	<b>Perf. Status</b>
<b>9327'-9573'</b>	<b>.40</b>	<b>63</b>	<b>Open</b>
<b>9073'-9297'</b>	<b>.40</b>	<b>66</b>	<b>Open</b>
<b>8783'-9039'</b>	<b>.40</b>	<b>69</b>	<b>Open</b>
<b>8587'-8746'</b>	<b>.40</b>	<b>45</b>	<b>Open</b>

**28. Acid, Fracture, Treatment, Cement Squeeze, Etc.**

<b>Depth Interval</b>	<b>Amount and Type of Material</b>
<b>9605'-9839'</b>	<b>5000 gal acid, 3000# 100 mesh, 150600# 30/50 TLC</b>
<b>9327'-9573'</b>	<b>5000 gal acid, 3000# 100 mesh, 150700# 30/50 TLC</b>
<b>9073'-9297'</b>	<b>5000 gal acid, 3000# 100 mesh, 150620# 30/50 TLC</b>
<b>8783'-9039'</b>	<b>5000 gal acid, 3000# 100 mesh, 150660# 30/50 White</b>
<b>8587'-8746'</b>	<b>5000 gal acid, 2800# 100 mesh, 150160# 30/50 White</b>



**Company:** EP Energy  
**Well:** Karren Trust 4-30C4  
**Location:** Duchesne, UT  
**Rig:** Precision 406

**Job Number:** \_\_\_\_\_  
**Mag Decl.:** \_\_\_\_\_  
**Dir Driller:** \_\_\_\_\_  
**MWD Eng:** \_\_\_\_\_

**Calculation Method** Minimum Curvature  
**Proposed Azimuth** 0.00  
**Depth Reference** KB  
**Tie Into:** Gyro/MWD

Survey Number	Survey Depth (ft)	Inclination (deg)	Azimuth (deg)	Course Length (ft)	True Vertical Depth (ft)	Vertical Section (ft)	Coordinates		Closure		Dogleg Severity (d/100')	Build Rate (d/100')	Walk Rate (d/100')	
							N/S (ft)	E/W (ft)	Distance (ft)	Direction Azimuth				
Tie In	0.00	0.00	0.00											
1	100.00	0.21	107.03	100.00	100.00	-0.05	0.05	S	0.17	E	0.18	107.03	0.21	107.03
2	200.00	0.21	198.31	100.00	200.00	-0.28	0.28	S	0.29	E	0.41	134.30	0.30	91.28
3	300.00	0.18	205.85	100.00	300.00	-0.60	0.60	S	0.16	E	0.62	164.79	0.04	-0.03
4	400.00	0.33	181.64	100.00	400.00	-1.03	1.03	S	0.09	E	1.03	175.19	0.18	-24.21
5	500.00	0.48	197.20	100.00	499.99	-1.72	1.72	S	0.05	W	1.72	181.53	0.19	15.56
6	600.00	0.63	184.76	100.00	599.99	-2.67	2.67	S	0.22	W	2.68	184.62	0.19	-12.44
7	700.00	0.55	205.50	100.00	699.98	-3.65	3.65	S	0.47	W	3.68	187.31	0.23	-0.08
8	800.00	0.43	202.12	100.00	799.98	-4.44	4.44	S	0.82	W	4.51	190.44	0.12	-0.12
9	900.00	0.43	204.62	100.00	899.98	-5.13	5.13	S	1.12	W	5.25	192.28	0.02	0.00
10	1000.00	0.41	174.71	100.00	999.98	-5.83	5.83	S	1.24	W	5.96	192.02	0.22	-0.02
11	1100.00	0.67	172.91	100.00	1099.97	-6.77	6.77	S	1.14	W	6.86	189.54	0.26	-1.81
12	1200.00	0.74	188.53	100.00	1199.96	-7.99	7.99	S	1.16	W	8.07	188.27	0.21	0.08
13	1300.00	0.63	195.51	100.00	1299.96	-9.16	9.16	S	1.40	W	9.26	188.72	0.14	-0.12
14	1400.00	0.80	191.75	100.00	1399.95	-10.37	10.37	S	1.69	W	10.51	189.27	0.18	-3.76
15	1500.00	0.87	198.60	100.00	1499.94	-11.78	11.78	S	2.08	W	11.96	190.01	0.12	0.07
16	1600.00	1.02	208.10	100.00	1599.92	-13.28	13.28	S	2.74	W	13.56	191.65	0.21	0.14
17	1700.00	1.01	213.19	100.00	1699.91	-14.79	14.79	S	3.64	W	15.23	193.81	0.09	-0.01
18	1800.00	0.92	220.25	100.00	1799.89	-16.14	16.14	S	4.64	W	16.79	196.02	0.15	-0.09
19	1900.00	0.88	227.07	100.00	1899.88	-17.28	17.28	S	5.72	W	18.20	198.31	0.11	-0.04
20	2013.00	0.76	213.68	113.00	2012.87	-18.49	18.49	S	6.77	W	19.69	200.10	0.20	-0.11
21	2211.00	0.40	43.20	198.00	2210.87	-19.08	19.08	S	7.02	W	20.33	200.20	0.58	-0.18
22	2307.00	2.00	30.60	96.00	2306.84	-17.39	17.39	S	5.94	W	18.38	198.85	1.68	1.67
23	2402.00	3.00	17.20	95.00	2401.75	-13.59	13.59	S	4.36	W	14.27	197.79	1.21	1.05
24	2499.00	1.90	10.00	97.00	2498.66	-9.58	9.58	S	3.33	W	10.15	199.16	1.18	-1.13
25	2594.00	2.90	359.00	95.00	2593.58	-5.63	5.63	S	3.10	W	6.43	208.83	1.15	1.05
26	2690.00	1.80	340.30	96.00	2689.50	-1.78	1.78	S	3.65	W	4.06	243.98	1.38	-1.15
27	2786.00	2.40	341.70	96.00	2785.43	1.55	1.55	N	4.79	W	5.03	287.89	0.63	0.63
28	2882.00	2.90	348.10	96.00	2881.33	5.83	5.83	N	5.92	W	8.31	314.56	0.60	0.52
29	2979.00	2.20	329.10	97.00	2978.23	9.83	9.83	N	7.38	W	12.29	323.09	1.12	-0.72
30	3074.00	2.60	348.30	95.00	3073.15	13.50	13.50	N	8.76	W	16.09	327.04	0.94	0.42
31	3170.00	3.50	353.30	96.00	3169.01	18.55	18.55	N	9.54	W	20.86	332.78	0.98	0.94
32	3266.00	2.50	346.90	96.00	3264.88	23.50	23.50	N	10.36	W	25.68	336.21	1.10	-1.04
33	3362.00	2.60	347.00	96.00	3360.79	27.66	27.66	N	11.32	W	29.88	337.74	0.10	0.10
34	3459.00	3.40	351.50	97.00	3457.65	32.65	32.65	N	12.24	W	34.87	339.45	0.86	0.82
35	3555.00	2.20	339.70	96.00	3553.54	37.19	37.19	N	13.30	W	39.50	340.32	1.38	-1.25



**Company:** EP Energy  
**Well:** Karren Trust 4-30C4  
**Location:** Duchesne, UT  
**Rig:** Precision 406

**Job Number:** \_\_\_\_\_  
**Mag Decl.:** \_\_\_\_\_  
**Dir Driller:** \_\_\_\_\_  
**MWD Eng:** \_\_\_\_\_

**Calculation Method** Minimum Curvature  
**Proposed Azimuth** 0.00  
**Depth Reference** KB  
**Tie Into:** Gyro/MWD

Survey Number	Survey Depth (ft)	Inclination (deg)	Azimuth (deg)	Course Length (ft)	True Vertical Depth (ft)	Vertical Section (ft)	Coordinates		Closure		Dogleg Severity (d/100')	Build Rate (d/100')	Walk Rate (d/100')
							N/S (ft)	E/W (ft)	Distance (ft)	Direction Azimuth			
36	3651.00	2.80	349.90	96.00	3649.45	41.23	41.23 N	14.35 W	43.65	340.81	0.78	0.63	10.63
37	3747.00	3.20	4.30	96.00	3745.32	46.21	46.21 N	14.56 W	48.45	342.51	0.89	0.42	-360.00
38	3844.00	2.20	0.90	97.00	3842.21	50.77	50.77 N	14.33 W	52.75	344.24	1.04	-1.03	-3.51
39	3939.00	2.20	17.90	95.00	3937.14	54.33	54.33 N	13.74 W	56.04	345.81	0.68	0.00	17.89
40	4034.00	2.80	16.30	95.00	4032.05	58.29	58.29 N	12.53 W	59.62	347.87	0.64	0.63	-1.68
41	4130.00	3.10	359.10	96.00	4127.92	63.13	63.13 N	11.91 W	64.25	349.32	0.97	0.31	357.08
42	4226.00	1.90	350.10	96.00	4223.83	67.30	67.30 N	12.23 W	68.40	349.70	1.31	-1.25	-9.38
43	4322.00	2.50	31.60	96.00	4319.76	70.65	70.65 N	11.40 W	71.56	350.83	1.73	0.63	-331.77
44	4418.00	3.70	23.00	96.00	4415.62	75.28	75.28 N	9.09 W	75.83	353.11	1.34	1.25	-8.96
45	4515.00	1.80	30.70	97.00	4512.51	79.48	79.48 N	7.09 W	79.79	354.90	1.99	-1.96	7.94
46	4610.00	2.50	35.20	95.00	4607.44	82.45	82.45 N	5.14 W	82.61	356.43	0.76	0.74	4.74
47	4706.00	2.70	34.30	96.00	4703.34	86.03	86.03 N	2.66 W	86.07	358.23	0.21	0.21	-0.94
48	4803.00	2.10	23.20	97.00	4800.25	89.55	89.55 N	0.67 W	89.55	359.57	0.78	-0.62	-11.44
49	4899.00	1.60	331.00	96.00	4896.21	92.34	92.34 N	0.63 W	92.34	359.61	1.76	-0.52	320.63
50	4996.00	1.50	302.50	97.00	4993.18	94.21	94.21 N	2.35 W	94.24	358.57	0.79	-0.10	-29.38
51	5092.00	1.70	269.90	96.00	5089.14	94.88	94.88 N	4.84 W	95.00	357.08	0.96	0.21	-33.96
52	5188.00	1.70	261.20	96.00	5185.10	94.66	94.66 N	7.67 W	94.97	355.37	0.27	0.00	-9.06
53	5284.00	1.70	256.90	96.00	5281.06	94.12	94.12 N	10.46 W	94.70	353.66	0.13	0.00	-4.48
54	5381.00	2.00	244.00	97.00	5378.01	93.05	93.05 N	13.38 W	94.01	351.81	0.53	0.31	-13.30
55	5476.00	1.90	225.70	95.00	5472.95	91.22	91.22 N	16.00 W	92.62	350.05	0.66	-0.11	-19.26
56	5573.00	2.40	214.20	97.00	5569.88	88.42	88.42 N	18.29 W	90.29	348.31	0.68	0.52	-11.86
57	5667.00	2.70	209.00	94.00	5663.79	84.86	84.86 N	20.47 W	87.29	346.44	0.40	0.32	-5.53
58	5764.00	2.90	207.80	97.00	5760.68	80.69	80.69 N	22.73 W	83.83	344.27	0.21	0.21	-1.24
59	5861.00	2.90	203.40	97.00	5857.55	76.27	76.27 N	24.84 W	80.21	341.96	0.23	0.00	-4.54
60	5955.00	3.10	206.10	94.00	5951.42	71.80	71.80 N	26.91 W	76.68	339.46	0.26	0.21	2.87
61	6052.00	2.20	223.80	97.00	6048.32	68.10	68.10 N	29.35 W	74.16	336.69	1.24	-0.93	18.25
62	6148.00	2.90	212.20	96.00	6144.22	64.72	64.72 N	31.92 W	72.16	333.75	0.90	0.73	-12.08
63	6244.00	3.20	208.90	96.00	6240.09	60.32	60.32 N	34.51 W	69.49	330.22	0.36	0.31	-3.44
64	6340.00	1.80	205.00	96.00	6335.99	56.60	56.60 N	36.44 W	67.32	327.23	1.47	-1.46	-4.06
65	6436.00	2.10	196.50	96.00	6431.94	53.55	53.55 N	37.58 W	65.42	324.94	0.43	0.31	-8.85
66	6532.00	2.90	193.20	96.00	6527.85	49.50	49.50 N	38.63 W	62.79	322.03	0.85	0.83	-3.44
67	6628.00	3.20	190.80	96.00	6623.71	44.50	44.50 N	39.69 W	59.63	318.27	0.34	0.31	-2.50
68	6725.00	2.40	201.30	97.00	6720.59	39.95	39.95 N	40.93 W	57.20	314.30	0.98	-0.82	10.82
69	6820.00	3.10	196.70	95.00	6815.48	35.64	35.64 N	42.39 W	55.38	310.05	0.77	0.74	-4.84
70	6917.00	2.90	195.70	97.00	6912.35	30.76	30.76 N	43.81 W	53.53	305.08	0.21	-0.21	-1.03
71	7013.00	3.20	193.20	96.00	7008.22	25.82	25.82 N	45.08 W	51.95	299.80	0.34	0.31	-2.60
72	7109.00	2.50	205.10	96.00	7104.10	21.31	21.31 N	46.58 W	51.22	294.59	0.95	-0.73	12.40



**Company:** EP Energy  
**Well:** Karren Trust 4-30C4  
**Location:** Duchesne, UT  
**Rig:** Precision 406

**Job Number:** \_\_\_\_\_  
**Mag Decl.:** \_\_\_\_\_  
**Dir Driller:** \_\_\_\_\_  
**MWD Eng:** \_\_\_\_\_

**Calculation Method** Minimum Curvature  
**Proposed Azimuth** 0.00  
**Depth Reference** KB  
**Tie Into:** Gyro/MWD

Survey Number	Survey Depth (ft)	Inclination (deg)	Azimuth (deg)	Course Length (ft)	True Vertical Depth (ft)	Vertical Section (ft)	Coordinates				Closure		Dogleg Severity (d/100')	Build Rate (d/100')	Walk Rate (d/100')
							N/S (ft)		E/W (ft)		Distance (ft)	Direction Azimuth			
73	7205.00	3.20	197.00	96.00	7199.98	16.85	16.85	N	48.25	W	51.11	289.25	0.84	0.73	-8.44
74	7301.00	2.10	168.80	96.00	7295.88	12.57	12.57	N	48.69	W	50.29	284.47	1.74	-1.15	-29.38
75	7397.00	2.90	175.30	96.00	7391.79	8.42	8.42	N	48.15	W	48.88	279.92	0.88	0.83	6.77
76	7493.00	2.40	162.30	96.00	7487.68	4.08	4.08	N	47.34	W	47.52	274.93	0.81	-0.52	-13.54
77	7589.00	3.30	168.30	96.00	7583.56	-0.54	0.54	S	46.17	W	46.17	269.34	0.99	0.94	6.25
78	7686.00	2.70	171.80	97.00	7680.43	-5.53	5.53	S	45.28	W	45.62	263.04	0.65	-0.62	3.61
79	7782.00	3.30	172.40	96.00	7776.30	-10.51	10.51	S	44.59	W	45.81	256.74	0.63	0.63	0.62
80	7878.00	2.70	151.60	96.00	7872.17	-15.24	15.24	S	43.15	W	45.76	250.55	1.28	-0.63	-21.67
81	7974.00	3.30	167.20	96.00	7968.04	-19.92	19.92	S	41.46	W	46.00	244.34	1.05	0.63	16.25
82	8070.00	1.70	180.90	96.00	8063.95	-24.04	24.04	S	40.87	W	47.42	239.54	1.77	-1.67	14.27
83	8166.00	0.70	116.50	96.00	8159.93	-25.72	25.72	S	40.37	W	47.87	237.50	1.60	-1.04	-67.08
84	8262.00	2.60	171.60	96.00	8255.89	-28.14	28.14	S	39.53	W	48.52	234.55	2.37	1.98	57.40
85	8358.00	1.60	154.70	96.00	8351.82	-31.51	31.51	S	38.64	W	49.85	230.81	1.21	-1.04	-17.60
86	8400.00	1.36	148.02	42.00	8393.81	-32.46	32.46	S	38.12	W	50.07	229.59	0.71	-0.58	-15.90
87	8500.00	1.16	154.83	100.00	8493.78	-34.38	34.38	S	37.07	W	50.55	227.15	0.24	-0.19	6.81
88	8600.00	1.28	161.14	100.00	8593.76	-36.35	36.35	S	36.27	W	51.35	224.94	0.17	0.11	6.30
89	8700.00	1.35	176.55	100.00	8693.73	-38.58	38.58	S	35.84	W	52.66	222.90	0.36	0.08	15.41
90	8800.00	1.51	178.32	100.00	8793.70	-41.07	41.07	S	35.73	W	54.44	221.02	0.17	0.16	1.77
91	8900.00	1.83	193.65	100.00	8893.66	-43.94	43.94	S	36.07	W	56.85	219.38	0.55	0.32	15.34
92	9000.00	2.35	188.35	100.00	8993.59	-47.52	47.52	S	36.75	W	60.07	217.71	0.55	0.51	-5.30
93	9100.00	2.69	184.67	100.00	9093.50	-51.89	51.89	S	37.24	W	63.87	215.66	0.38	0.35	-3.68
94	9200.00	2.65	185.66	100.00	9193.39	-56.54	56.54	S	37.66	W	67.93	213.67	0.06	-0.04	0.99
95	9300.00	2.92	190.29	100.00	9293.27	-61.34	61.34	S	38.34	W	72.34	212.01	0.35	0.26	4.63
96	9400.00	2.63	192.17	100.00	9393.15	-66.09	66.09	S	39.28	W	76.88	210.72	0.30	-0.29	1.88
97	9500.00	2.85	193.24	100.00	9493.04	-70.75	70.75	S	40.33	W	81.44	209.68	0.23	0.23	1.07
98	9600.00	2.59	193.04	100.00	9592.93	-75.38	75.38	S	41.41	W	86.00	208.78	0.26	-0.26	-0.20
99	9700.00	2.75	190.75	100.00	9692.82	-79.94	79.94	S	42.37	W	90.47	207.92	0.19	0.16	-2.29
100	9800.00	2.57	187.59	100.00	9792.71	-84.51	84.51	S	43.11	W	94.87	207.03	0.23	-0.18	-3.15
101	9900.00	2.59	187.71	100.00	9892.61	-88.97	88.97	S	43.71	W	99.13	206.16	0.03	0.02	0.12
102	10000.00	2.75	186.59	100.00	9992.50	-93.59	93.59	S	44.29	W	103.54	205.32	0.16	0.15	-1.12
103	10100.00	2.75	182.94	100.00	10092.38	-98.37	98.37	S	44.69	W	108.04	204.43	0.17	0.00	-3.65
104	10200.00	2.62	184.07	100.00	10192.27	-103.05	103.05	S	44.97	W	112.43	203.58	0.14	-0.13	1.13
105	10300.00	2.42	180.00	100.00	10292.18	-107.44	107.44	S	45.13	W	116.54	202.79	0.27	-0.20	-4.06
106	10400.00	2.77	185.69	100.00	10392.08	-111.96	111.96	S	45.37	W	120.80	202.06	0.44	0.36	5.69
107	10500.00	2.86	182.95	100.00	10491.95	-116.86	116.86	S	45.74	W	125.49	201.38	0.16	0.09	-2.74
108	10600.00	2.54	185.08	100.00	10591.84	-121.55	121.55	S	46.07	W	129.99	200.76	0.34	-0.33	2.13
109	10700.00	2.63	182.08	100.00	10691.74	-126.05	126.05	S	46.35	W	134.30	200.19	0.16	0.09	-3.00



**Company:** EP Energy  
**Well:** Karren Trust 4-30C4  
**Location:** Duchesne, UT  
**Rig:** Precision 406

**Job Number:** \_\_\_\_\_  
**Mag Decl.:** \_\_\_\_\_  
**Dir Driller:** \_\_\_\_\_  
**MWD Eng:** \_\_\_\_\_

**Calculation Method** Minimum Curvature  
**Proposed Azimuth** 0.00  
**Depth Reference** KB  
**Tie Into:** Gyro/MWD

Survey Number	Survey Depth (ft)	Inclination (deg)	Azimuth (deg)	Course Length (ft)	True Vertical Depth (ft)	Vertical Section (ft)	Coordinates		Closure Distance (ft)	Direction Azimuth	Dogleg Severity (d/100')	Build Rate (d/100')	Walk Rate (d/100')
							N/S (ft)	E/W (ft)					
110	10800.00	2.64	184.78	100.00	10791.64	-130.63	130.63 S	46.62 W	138.70	199.64	0.13	0.02	2.71
111	10900.00	2.52	184.45	100.00	10891.53	-135.12	135.12 S	46.98 W	143.06	199.17	0.12	-0.12	-0.33
112	10925.00	2.70	186.65	25.00	10916.51	-136.26	136.26 S	47.09 W	144.17	199.07	0.81	0.70	8.78
113	11103.00	2.70	186.65	178.00	11094.31	-144.58	144.58 S	48.06 W	152.36	198.39	0.00	0.00	0.00



## CENTRAL DIVISION

ALTAMONT FIELD  
KARREN TRUST 4-30C4  
KARREN TRUST 4-30C4  
DRILLING LAND

### Operation Summary Report

Disclaimer: Although the information contained in this report is based on sound engineering practices, the copyright owner(s) does (do) not accept any responsibility whatsoever, in negligence or otherwise, for any loss or damage arising from the possession or use of the report whether in terms of correctness or otherwise. The application, therefore, by the user of this report or any part thereof, is solely at the user's own risk.

## 1 General

### 1.1 Customer Information

Company	CENTRAL DIVISION
Representative	
Address	

### 1.2 Well Information

Well	KARREN TRUST 4-30C4		
Project	ALTAMONT FIELD	Site	KARREN TRUST 4-30C4
Rig Name/No.	PRECISION DRILLING/406	Event	DRILLING LAND
Start date	4/13/2015	End date	
Spud Date/Time	4/15/2015	UWI	KARREN TRUST 4-30C4
Active datum	KB @5,820.8ft (above Mean Sea Level)		
Afe No./Description	163172/53664 / KARREN TRUST 4-30C4		

## 2 Summary

### 2.1 Operation Summary

Date	Time Start-End	Duration (hr)	Phase	Activity	Sub	OP Code	MD from (ft)	Operation
3/27/2015	6:00 8:00	2.00	CASCOND	24		P	0.0	SET 57' 20" CONDUCTOR, SET MOUSE HOLE @ 80'. ADDED RKB CORRECTION FOR PD 406.
	8:00 11:30	3.50	CASSURF	24		P	57.0	DRILL 12¼" HOLE TO 2,137'. RAN 52 JTS 9-5/8" 40# N-80 LT&C TO 2,110'. FC @ 2,071' SHOE 2,110'. ADDED RKB CORRECTION FOR PD 406.
	11:30 14:30	3.00	CASSURF	25		P	2,137.0	M&P PUMPED 20 BBLS H2O. 460 SXS ( 194 BBLS ) VARICEM LEAD CMT @ 12 PPG, 2.37 YLD TAILED WITH 200 SXS ( 46.3 BBLS ) OF HALCEM CMT @ 14.3 PPG, 1.30 YIELD. RELEASED TOP PLUG. DISPLACED WITH 156 BBLS OF H2O @ 4 BPM. BUMPED PLUG @ 14:25HRS 3/27/15 WITH 1,078 PSI. ¾ BBL BLED BACK, FLOATS HELD. GOOD RETURNS THROUGHOUT JOB.
	14:30 6:00	15.50	CASSURF	25		P	2,137.0	WOC, NO FALL. RIG DOWN & CLEAR LOCATION.
4/13/2015	6:00 6:00	24.00	MIRU	01		P	2,137.0	MOVE IN & RIG UP. 100% MOVED IN 65% RIGGED UP. RELEASED TRUCKS @ 20:00 HRS 4/12/15.
4/14/2015	6:00 21:00	15.00	MIRU	01		P	2,137.0	PREP FLOOR & DERRICK. PU TDU. 100% RIGGED UP. RUN STEAM LINE. PERFORM RIG INSPECTION. RIG ON RATE @ 21:00 HRS 4/13/15.
	21:00 4:00	7.00	CASSURF	28		P	2,137.0	NU 11" 10M BOPE & INSTALL FLOW LINE. PJSM. TORQUE BOLTS W/ WEATHERFORD. RU TEST UNIT.
	4:00 6:00	2.00	CASSURF	19		P	2,137.0	TEST 11" 5M ANNULAR TO 250 / 2,500 PSI AND REMAINING BOPE, FLOOR VALVES, ETC TO 250 / 5,000 PSI. TESTED CHOKE MANIFOLD TO 250 / 10,000 PSI. HELD EACH TEST 10 MINUTES.
4/15/2015	6:00 8:30	2.50	CASSURF	19		P	2,137.0	TESTED 11" 5M ANNULAR TO 250 / 2,500 PSI AND REMAINING BOPE, FLOOR VALVES, ETC TO 250 / 5,000 PSI. TESTED CHOKE MANIFOLD TO 250 / 10,000 PSI. HELD EACH TEST 10 MINUTES. MANUAL CHOKE VALVE FAILED.
	8:30 9:30	1.00	CASSURF	31		P	2,137.0	TEST CASING TO 2,500 PSI FOR 30 MINUTES. TEST GOOD.
	10:30 11:30	1.00	CASSURF	48		N	2,137.0	REMOVE CHOKE VALVE.
	11:30 13:30	2.00	CASSURF	14		P	2,137.0	PU 8¾" BHA & RACK BACK.
	13:30 14:30	1.00	CASSURF	48		N	2,137.0	INSTALL CHOKE VALVE.
	14:30 17:00	2.50	CASSURF	19		P	2,137.0	TESTED HCR & MANUAL CHOKE TO 250 / 5,000 PSI. HELD EACH TEST 10 MINUTES. INSTALL WEAR BUSHING.

## 2.1 Operation Summary (Continued)

Date	Time Start-End	Duratio n (hr)	Phase	Activit y	Sub	OP Code	MD from (ft)	Operation
	17:00 20:30	3.50	CASSURF	14		P	2,137.0	MU BIT & TIH WITH BHA, PU 4.5" DP TO 2,013'.
	20:30 21:30	1.00	CASSURF	17		P	2,137.0	S & C DRILL LINE.
	21:30 22:30	1.00	CASSURF	12		P	2,137.0	SERVICED RIG & TDU.
	22:30 23:30	1.00	CASSURF	43		N	2,137.0	CHANGE OUT HYDRAULIC RAM ON EXTEND BUSHING.
	22:30 0:30	2.00	CASSURF	32		P	2,137.0	DRILL OUT CMT, FE & 10'.
	0:30 1:00	0.50	CASSURF	33		P	2,147.0	CBU & PERFORM FIT TO 14.8 EMW WITH 9.7 PPG MUD @ 570 PSI.
	1:00 6:00	5.00	DRLINT1	07		P	2,147.0	DRILLED 2,147' - 2,645'. SPUD @ 1:00 4/15/15.
4/16/2015	6:00 7:00	1.00	DRLINT1	07		P	2,645.0	DRILLED 2,645' - 2,925'.
	7:00 7:30	0.50	DRLINT1	12		P	2,925.0	SERVICED RIG & TD.
	7:30 13:30	6.00	DRLINT1	07		P	2,925.0	DRILLED 2,925' - 3,606'.
	13:30 14:00	0.50	DRLINT1	57		N	3,606.0	TROUBLE SHOOT RYAN MWD TOOLS.
	14:00 23:00	9.00	DRLINT1	07		P	3,606.0	DRILLED 3,606' - 4,757'.
	23:00 23:30	0.50	DRLINT1	12		P	4,757.0	SERVICED RIG & TD.
	23:30 6:00	6.50	DRLINT1	07		P	4,757.0	DRILLED 4,757' - 5,750'.
4/17/2015	6:00 14:30	8.50	DRLINT1	07		P	5,750.0	DRILLED F/ 5,750' T/ 6,545'.
	14:30 15:00	0.50	DRLINT1	12		P	6,545.0	SERVICED RIG & TD.
	15:00 3:00	12.00	DRLINT1	07		P	6,545.0	DRILLED F/ 6,545' T/ 7,352'.
	3:00 3:30	0.50	DRLINT1	12		P	7,352.0	SERVICED RIG & TD.
	3:30 6:00	2.50	DRLINT1	07		P	7,352.0	DRILLED F/ 7,352' T/ 7,545'.
4/18/2015	6:00 15:00	9.00	DRLINT1	07		P	7,545.0	DRILLED F/ 7,545' T/ 7,929'.
	15:00 15:30	0.50	DRLINT1	12		P	7,929.0	SERVICED RIG & TD.
	15:30 3:00	11.50	DRLINT1	07		P	7,929.0	DRILLED F/ 7,929' T/ 8,453'. INT TD @ 03:00 4/18/15. 22' FT UNSEEN SLIDE IN THE HOLE.
	3:00 4:30	1.50	DRLINT1	15		P	8,453.0	SIMULATE CONNECTION. CIRC BU. MAX GAS 134 UNITS (3RD PARTY), 52 UNITS (PASON). CHECKED FLOW.
	4:30 6:00	1.50	DRLINT1	13		P	8,453.0	WIPER TRIP.
4/19/2015	6:00 15:00	9.00	DRLINT1	13		P	8,453.0	FINISH WIPER TRIP. FLOW CHECKS @ 2,100', 5,000', 8,453'. NO BACK REAMING ON TRIP.
	15:00 16:30	1.50	DRLINT1	15		P	8,453.0	C & C MUD. PASON BU GAS = 4118 UNITS, 3 RD PARTY BU GAS = 2503 UNITS. CHECKED FLOW (NEG), PUMPED SLUG.
	16:30 0:00	7.50	DRLINT1	14		P	8,453.0	L/D DP. CHECKED FLOW @ 6,000', 4,000', 2,000', 821'.
	0:00 0:30	0.50	DRLINT1	12		P	8,453.0	CLEANED RIG FLOOR OF 4 1/2" EQUIPMENT.
	0:30 1:00	0.50	DRLINT1	42		P	8,453.0	PULLED WEAR BUSHING, CHANGED OUT BAILS & ELEVATORS. REDUCED MW IN PITS F/ 9.9 PPG 45 VIS T/ 9.6 PPG 40 VIS.
	1:00 2:00	1.00	CASINT1	24		P	8,453.0	PJSM. RU FRANKS CASING CREW & TORQUE TURN.
	2:00 6:00	4.00	CASINT1	24		P	8,453.0	MU SHOE TRACK & TEST. RAN 47 JTS 7" 29# HCP-110 LT&C CSG TO 2,000'. BREAK CIRC EVERY 1,000'. CBU EVERY 2,000'.
4/20/2015	6:00 17:30	11.50	CASINT1	24		P	8,453.0	RAN 203 JTS 7" 20# HCP-110 LT&C CSG TO 8,453'. FLOAT COLLAR @ 8,410', MARKER JT @ 6,503'. CBU @ SHOE. BREAK CIRC EVERY 1,000' & CIRC BU 2,000'. NO LOSSES. PU TAG JT TAG BOTTOM @ 8,453'. LD TAG JT. SPACED OUT W/ 10' PUP JT & LANDING JT.
	17:30 19:00	1.50	CASINT1	15		P	8,453.0	C & C MUD @ 1 - 6 BPM. MAX GAS 2500 UNITS. NO FLARE. NO LOSSES. FINAL CIRC PRESSURE 460 PSI. HELD PJSM FOR CEMENT OPS.

## 2.1 Operation Summary (Continued)

Date	Time Start-End	Duration (hr)	Phase	Activity	Sub	OP Code	MD from (ft)	Operation
	19:00 22:30	3.50	CASINT1	25		P	8,453.0	RU HES CEMENTERS. PUMPED 47 BBLS 10.0 PPG TUNED SPACER . 670 SX ( 228.0 BBLS ) EXTENDACEM LEAD CMT @ 12.5 PPG, 1.91 YLD TAILED WITH 305 SXS ( 89 BBLS ) OF EXPANDACHEM CMT @ 13 PPG, 1.64 YIELD. RELEASED TOP PLUG. DISPLACED WITH 312 BBLS OF 9.7 PPG MUD @ 6 - 3 BPM. BUMPED PLUG @ 21:33 HRS 4/19/15 WITH 2200 PSI. 2.5 BBL BLED BACK, FLOATS HELD. RD CEMENTERS. RETURNS SLOWED LAST 90 BBLS DISP, TOTAL LOST 60 BBLS DURING CMT OPS. 20 BBLS SPACER CAME BACK TO SURFACE. EST TOC 1,800'.
	22:30 23:30	1.00	CASINT1	27		P	8,453.0	LD LANDING JT. INSTALLED & TEST PACK-OFF TO 5,000 PSI FOR 15 MIN.
	23:30 0:30	1.00	CASINT1	31		P	8,453.0	TESTED CASING TO 2,500 PSI HOLD FOR FOR 30 MINUTES.
	0:30 2:30	2.00	CASINT1	42		P	8,453.0	CHANGED OUT IBOP, TDU SAVER SUB TO 4" XT-39, BAILS, & 4" ELEVATORS.
	2:30 6:00	3.50	CASINT1	19		P	8,453.0	PJSM. RU WEATHERFORD TESTERS & TESTED 11" 5M ANNULAR TO 250 / 4,000 PSI, RAMS & REMAINING BOPE, FLOOR VALVES, ETC TO 250 / 10,000 PSI. HOLD EACH TEST 10 MINUTES.
4/21/2015	6:00 8:30	2.50	CASINT1	19		P	8,453.0	PJSM. RU WEATHERFORD TESTERS & TESTED 11" 5M ANNULAR TO 250 / 4,000 PSI, RAMS & REMAINING BOPE, FLOOR VALVES, ETC TO 250 / 10,000 PSI. HOLD EACH TEST 10 MINUTES.
	8:30 9:30	1.00	CASINT1	12		P	8,453.0	SERVICE RIG & TD. CLEANED FLOOR & PREPARED TO PU BHA & 4" DP.
	9:30 19:00	9.50	CASINT1	14		P	8,453.0	PU BHA & 4" XT 39 DP. TIH T/ 8,300'.
	19:00 20:30	1.50	CASINT1	42		P	8,453.0	S & C DRILL LINE
	20:30 21:00	0.50	CASINT1	31		P	8,453.0	PRE FIT CASING TEST (1930 PSI).
	21:00 22:30	1.50	CASINT1	32		P	8,453.0	DRILL FE & CMT.
	22:30 23:00	0.50	DRLPRD	07		P	8,453.0	DRILLED F/ 8,453' T/ 8,463'.
	23:00 23:30	0.50	DRLPRD	15		P	8,463.0	CIRC BU.
	23:30 0:00	0.50	DRLPRD	33		P	8,463.0	PREFORMED FIT. 14.8 PPG EMW. PUMPED INTO FORMATION @ 1680 PSI W/ 11.0 PPG MW.
	0:00 4:00	4.00	DRLPRD	07		P	8,463.0	DRILLED F/ 8,463' T/ 8,900'.
	4:00 4:30	0.50	DRLPRD	15		P	8,900.0	CIRC BU F/ WIRELINE SURVEY.
	4:30 5:30	1.00	DRLPRD	11		P	8,900.0	RUN WIRELINE SURVEY @ 8869'.
	5:30 6:00	0.50	DRLPRD	07		P	8,900.0	DRILLED F/ 8,900' T/ 8,995'.
4/22/2015	6:00 14:00	8.00	DRLPRD	07		P	8,995.0	DRILLED F/ 8,995' T/ 9,751'.
	14:00 14:30	0.50	DRLPRD	12		P	9,751.0	SERVICED RIG & TD.
	14:30 20:00	5.50	DRLPRD	07		P	9,751.0	DRILLED F/ 9,721' T/ 10,324'.
	20:00 20:30	0.50	DRLPRD	12		P	10,324.0	SERVICED RIG & TD.
4/23/2015	20:30 6:00	9.50	DRLPRD	07		P	10,324.0	DRILLED F/ 10,324' T/ 11,103'. TD @ 06:00 HRS 4-22-15.
	6:00 7:00	1.00	DRLPRD	15		P	11,103.0	C & C MUD. RMW F/ 11.9 PPG T/ 12.1 PPG. FLOW CK (NEG).
	7:00 11:00	4.00	DRLPRD	13		P	11,103.0	WIPER TRIP TO 8,450'.
	11:00 14:30	3.50	DRLPRD	15		P	11,103.0	C & C MUD. MAX GAS 6944 UNITS (PASON), 2429 UNITS (MUD LOGGER) , MUD CUT 11.4 PPG F/ 12.1 PPG.. RAISE MW F/ 12.1 PPG T 12.3 PPG. VIS 45 FLOW CK.
	14:30 20:30	6.00	DRLPRD	13		P	11,103.0	TOH TO LOG & RUN 5" LINER. FLOW CK @ 11,103, 8500, 6000 3500, LD BIT STAB'S & PONY COLLAR
	20:30 21:00	0.50	DRLPRD	13		P	11,103.0	CLEANED RIG FLOOR & CAT WALK.
	21:00 3:00	6.00	EVLPRD	22		P	11,103.0	PJSM. RU & RUN HALLIBURTONS ULTRA SLIM COMBO. LOGGER'S DEPTH 11,100' LOG UP TO 2000'. RD HES LOGGING UNIT. REDUCED MW F/ 12.3 PPG T/ 11.9 PPG 40 VIS WHILE LOGGING.
	3:00 4:00	1.00	CASPRD1	24		P	11,103.0	PJSM. RU FRANKS CSG CREW & TORQUE TURN.

## 2.1 Operation Summary (Continued)

Date	Time Start-End	Duration (hr)	Phase	Activity	Sub	OP Code	MD from (ft)	Operation
	4:00 6:00	2.00	CASPRD1	24		P	11,103.0	MADE UP 5" 18# HCP110 STL SHOE TRACK. TESTED SHOE TRACK. PU 5" 18# HCP110 STL. 886' AT REPORT TIME. VAM REP (CLIFF) SUPERVISING LINER OPERATIONS.
4/24/2015	6:00 22:30	16.50	CASPRD1	13		P	11,103.0	FINISH PU 5" LINER. TOTAL LINER 2,790'. TIH W/ 5" LINER ON 4" DP @ 70 FPM. FILL EVERY 1,000'. & CIRC BU EVERY 2,000'.. TAG BOTTOM W/ 10 K. SPACE OUT & RU CEMENT HEAD.
	22:30 1:30	3.00	CASPRD1	15		P	11,103.0	CIRC 2X BU. INITIAL RATE 1.1 BPM, INCREASED TO 2.5 BPM, PRESSURE LEVELED OFF AFTER 1 BU. MAX GAS 8114 UNITS PASON. 10.7 PPG MC. BG GAS 376 UNITS. FINAL CIRC PRESSURE 421 PSI @ 2.5 BPM. NO LOSSES DURING CIRCULATION. HELD PJSM ON CEMENT OPERATIONS.
	1:30 3:30	2.00	CASPRD1	25		P	11,103.0	RU HES & TESTED LINES TO 9,500 PSI. PUMPED 20 BBLS 12.2 PPG TUNED SPACER & 215 SKS ( 66 BBLS) 14.2 PPG WITH 1.52 YIELD EXPANDACEM CMT. WASHED LINES. DROPPED DP DART. PUMPED 60 BBLS H2O WITH 2% KCL 0.1 % BIOCIDES, 74 BBLS 11.9 PPG MUD. BUMPED PLUG WITH 2800 PSI @ 04:00 HRS 4/24/15. CHECKED FLOATS, FLOATS HELD, 1.25 BBLS BLEED BACK. NO LOSSES DURING CMT OPS. EST TOC 8,313'.
	3:30 4:30	1.00	CASPRD1	25		P	11,103.0	RELEASED BALL, RUPTURE DISC @ 5200 PSI. PUMPED 45 BBLS, PRESSURED TO 7900 PSI, EXPANDED HANGER. PULL TESTED LINER WITH 80K OVERPULL. SAT DOWN 90K , RELEASED SETTING TOOL FROM LINER HANGER. LANDED FS @ 11,098, FC @11,047', LC @ 10,998'. TOL @ 8307'. 146' OF LAP. TOTAL LINER 2790'. MARKER JT TOPS @ 10,079' & 9,085'.
	4:30 5:30	1.00	CASPRD1	15		P	11,103.0	PULLED UP TO TOL. OBSERVED 2 OVERPULLS OF 10K THROUGH SEALS. CIRC 1.5 TIMES ANNULAR VOLUME. 20 BBLS WEIGHTED SPACER & 20 BBLS WEIGHTED CEMENT TO SURFACE. CHECKED FLOW (NEG). POSITIVE TEST TOL TO 1,000 PSI FOR 10MIN. TEST OK.
	5:30 6:00	0.50	CASPRD1	15		P	11,103.0	DISPLACING MUD OUT OF THE HOLE WITH WATER.
	6:00 8:00	2.00	CASPRD1	15		P	11,103.0	PUMPED 350 BBLS H2O WITH NO ADDITIVES, 250 BBLS H2O WITH 2% KCL 0.1 % BIOCIDES TILL CLEAN RETURNS. RD HES.
4/25/2015	8:00 19:30	11.50	CASPRD1	14		P	11,103.0	LD DP & LAY DOWN LINER SITTING TOOL. RUN DC'S & DP OUT OF DERRICK. LD DP & DC'S. CLEANED MUD TANKS.
	19:30 22:30	3.00	CASPRD1	29		P	11,103.0	PJSM. ND BOPE.
	22:30 0:30	2.00	CASPRD1	30		P	11,103.0	INSTALLED TBG HEAD & FRAC VALVE. TESTED HEAD TO 5,000 PSI FOR 10MIN. RIG RELEASED @ 00:30 HRS 4-25-15.
	0:30 6:00	5.50	RDMO	02		P	11,103.0	PREPARED RIG TO BE MOVED TO THE MILLETT 2-14C5
4/26/2015	6:00 6:00	24.00	RDMO	02		P	11,103.0	PREPARED PD 406 TO BE MOVED TO THE MILLETT 2-14C5.



Table of Contents

1	General.....	1
1.1	Customer Information.....	1
1.2	Well Information.....	1
2	Summary.....	1
2.1	Operation Summary.....	1

## CENTRAL DIVISION

ALTAMONT FIELD  
KARREN TRUST 4-30C4  
KARREN TRUST 4-30C4  
COMPLETION LAND

### Operation Summary Report

Disclaimer: Although the information contained in this report is based on sound engineering practices, the copyright owner(s) does (do) not accept any responsibility whatsoever, in negligence or otherwise, for any loss or damage arising from the possession or use of the report whether in terms of correctness or otherwise. The application, therefore, by the user of this report or any part thereof, is solely at the user's own risk.

## 1 General

### 1.1 Customer Information

Company	CENTRAL DIVISION
Representative	
Address	

### 1.2 Well Information

Well	KARREN TRUST 4-30C4		
Project	ALTAMONT FIELD	Site	KARREN TRUST 4-30C4
Rig Name/No.		Event	COMPLETION LAND
Start date	5/1/2015	End date	
Spud Date/Time	4/15/2015	UWI	KARREN TRUST 4-30C4
Active datum	KB @5,820.8ft (above Mean Sea Level)		
Afe No./Description	163172/53664 / KARREN TRUST 4-30C4		

## 2 Summary

### 2.1 Operation Summary

Date	Time Start-End	Duration (hr)	Phase	Activity	Sub	OP Code	MD from (ft)	Operation
5/1/2015	11:00 13:30	2.50	MIRU	01		P		MOVE RIG TO LOCATION. SPOT CATWALK & PIPE RACKS. UNLOAD TBG. NU BOP. RU RIG.
	13:30 18:30	5.00	WOR	24		P		TIH W/ 4-1/8" OD BIT, BIT SUB, 90 JTS 2-3/8"EUE TBG, X-OVER & 165 JTS 2-7/8"EUE TBG. SDFN
5/2/2015	6:00 7:00	1.00	WOR	28		P		CREW TRAVEL TO LOCATION HSM WRITE AND REVIEW JSA TOPIC; R/U POWER SWIVEL HAND PLACEMENT
	7:00 10:30	3.50	WOR	39		P		CONTINUE TIH TAG AT 10931' TMD R/U POWER SWIVEL ESTABLISH CIRC C/O TO 11003' TMD CIRC WELL CLEAN R/D POWER SWIVLE
	10:30 15:40	5.17	WOR	39		P		TOH L/D 250 JTS OF 2 7/8" TBG CHANGE HANDLING TOOLS 90-JTS OF 2 3/8" L/D BIT AND BIT SUB SECURE WELL CLOSE 7" MASTER VALVE
	15:40 15:40	0.00	WOR	16		P		R/D FLOOR N/D BOPE N/U NIGHT CAP AND 7" MASTER VLAVE RDMO
5/5/2015	6:00 7:00	1.00	WLWORK	28		P		CREW TRAVEL HSM WRITE & REVIEW JSA (TOPIC) TRIP HAZARDS
	7:00 13:00	6.00	WLWORK	18		P		R/U WIRELINE TRUCK & HOT OIL TRUCK, FILL CSG W/ 25 BBLs 2% KCL, RIH W/ CBL TOOL TO 11,100', PRESSURE UP TO 4000 PSI, POOH RUNNING CBL TO 100', BLEED OFF PRESSURE, R/D WIRELINE TRUCK & HOTOILER, SECURE WELL, SDFD
5/8/2015	6:00 7:30	1.50	WHDTRE	28		P		CREW TRAVEL HELD SAFETY MEETING ON NIPPLING UP FRAC VALVES. FILLED OUT JSA.
	7:30 12:30	5.00	WHDTRE	16		P		PRESSURE TEST CSG@ 9000 PSI FOR 30 MINS. HELD. NU FRAC VALVES AND PRESSURE TEST @ 10000 PSI HELD.
5/9/2015	6:00 7:30	1.50	WLWORK	28		P		CREW TRAVEL HELD SAFETY MEETING ON RIGGING UP WIRELINE (OVERHEAD HAZARDS). FILLED OUT JSA.
	7:30 11:00	3.50	WLWORK	21		P		MIRU WIRELINE PERFORATED STAGE #1 FROM 10946' TO 10601'. ALL PERFS CORRELATED TO CUTTERS RADIAL CBL, GAMMA RAY, CCL LOG RUN #1 DATED 04-MAY-2015. 23 NET FT. 69 SHOTS. 2 3/4" GUNS, 16 GM CHARGES, 3 SPF, 120 PHASING. STARTING PRESSURE 1000 PSI. FINAL PRESSURE 900 PSI. RD WIRELINE. CLOSED IN WELL CLOSED AND LOCKED FRAC VALVES CLOSED CSG VALVES AND INSTALL NIGHT CAPS.

## 2.1 Operation Summary (Continued)

Date	Time Start-End	Duratio n (hr)	Phase	Activit y	Sub	OP Code	MD from (ft)	Operation
5/10/2015	6:00 7:30	1.50	SITEPRE	28		P		CREW TRAVEL HELD SAFETY MEETING ON TRANSFERRING WATER. FILLED OUT JSA.
	7:30 13:30	6.00	SITEPRE	18		P		TRANSFERED WATER THRU CHOLRINE DIOXIDE UNIT. AND STARTED HEATING WATER.
	13:30 18:00	4.50	SITEPRE	18		P		FINISHED HEATING WATER AND REFILL STAGING AREA.
5/11/2015	6:00 6:30	0.50	SITEPRE	28		P		CREW TRAVEL HELD SAFETY MEETING ON HEATING WATER. FILLED OUT JSA.
	6:30 18:00	11.50	SITEPRE	18		P		FINISHED HEATING FRAC TANKS AND MIRU FRAC EQUIPMENT.
5/12/2015	6:00 7:00	1.00	MIRU	28		P		HELD SAFETY MEETING ON PUMPING HIGH PRESSURE. FILLED OUT JSA AND STARTED EQUIPMENT.
	7:00 9:00	2.00	STG01	35		P		PRESSURE TEST LINES @ 9650 PSI. OPENED UP WELL W/ 274 PSI. BREAK DOWN STAGE # 1 PERFS @ 4431 PSI, 9.8 BPM, 8 BBLS PUMPED. EST INJ RATE 35 BPM, 5100 PSI. STEP RATE TEST 26 OPEN PERFS. I.S.I.P. 3963 PSI. F.G. ..80, 5 MIN 3803 PSI, 10 MIN 3757 PSI. TREATED PERFS W/ 5000 GALS 15% HCL ACID. PUMPED 3100 LBS 100 MESH IN 1/2 PPG STAGE AND 150400 LBS TLC 30/50. IN .5#, 1#, 2# AND 3# STAGES. AVG RATE 65.6 BPM, MAX RATE 75.9 BPM. AVG PRESS 4951, MAX PRESS 7251. I.S.I.P. 4263 PSI. F.G. ..83. SHUT WELL IN 3928 BBLS TO RECOVER. TURNED WELL OVER TO WIRELINE
	9:00 14:00	5.00	STG02	26		N		RU WIRELINE RIH SET CBP @ 10550', UNABLE TO RELEASE FROM CBP.PERFORATE CSG FROM 10438.5' TO 10440.5'. WORKED PERF GUN FREE. PULLED UP TO 10059 GOT STUCK, WORKRED GUN FREE. POOH W/ GUN AND SETTING TOOL HAD SAND IN SETTING TOOL AND PERF GUNS.RIH W/ OLD PERF GUN. TAGGED @ 10548' WAS STICKY. POOH.
	14:00 16:00	2.00	STG02	21		P		RIH SET CBP @ 10428' W/ 4200 PSI. PERFORATED STAGE # 2 FROM 10519" TO 10209'. ALL PERFS CORRELATED TO CUTTERS RADIAL CBL, GAMMA RAY, CCL LOG RUN #1 DATED 04-MAY-2015. 23 NET FT. 69 SHOTS. 2 3/4" GUNS, 16 GM CHARGES, 3 SPF, 120 PHASING. STARTING PRESSURE 4200 PSI. FINAL PRESSURE 3500 PSI. TURNED WELL OVER TO FRAC CREW.
	16:00 17:30	1.50	STG02	35		P		PRESSURE TEST LINES @ 9350 PSI. OPENED UP WELL W/ 3197 PSI. BREAK DOWN STAGE # 2 PERFS @ 4528 PSI, 10 BPM, 12 BBLS PUMPED. EST INJ RATE 34.8 BPM, 5169 PSI. STEP RATE TEST 14 OPEN PERFS. I.S.I.P. 3755 PSI. F.G. ..795, 5 MIN 3517 PSI, 10 MIN 3483 PSI. TREATED PERFS W/ 5000 GALS 15% HCL ACID. PUMPED 3100 LBS 100 MESH IN 1/2 PPG STAGE AND 150400 LBS TLC 30/50. IN .5#, 1#, 2# AND 3# STAGES. AVG RATE 66.8 BPM, MAX RATE 75.6 BPM. AVG PRESS 4897, MAX PRESS 7200. I.S.I.P. 3466 PSI. F.G. .767. SHUT WELL IN 3883 BBLS TO RECOVER. TURNED WELL OVER TO WIRELINE
	17:30 20:00	2.50	STG03	21		P		RIH W/ WIRELINE CBP WAS FLOATING IN GEL, PULLED ABOVE LINER TOP WAIT 1 HR. RIH SET CBP @ 10195' W/ 4000 PSI. PERFORATED STAGE # 3 FROM 10180' TO 9870'. ALL PERFS CORRELATED TO CUTTERS RADIAL CBL, GAMMA RAY, CCL LOG RUN #1 DATED 04-MAY-2015. 23 NET FT. 69 SHOTS. 2 3/4" GUNS, 16 GM CHARGES, 3 SPF, 120 PHASING. STARTING PRESSURE 4000 PSI. FINAL PRESSURE 3900 PSI. SHUT IN WELL. CLOSED AND LOCKED ALL FRAC VALVES. CLOSED IN SURFACE CSG W/ TWO VALVES.
5/13/2015	6:00 6:30	0.50	STG03	28		P		HELD SAFETY MEETING ON PUMPING HIGH PRESSURE. BODY POSITIONING. FILLED OUT JSA

## 2.1 Operation Summary (Continued)

Date	Time Start-End	Duration (hr)	Phase	Activity	Sub	OP Code	MD from (ft)	Operation
	6:30 8:00	1.50	STG03	35		P		PRESSURE TEST LINES @ 9416 PSI. OPENED UP WELL W/ 3860 PSI. BREAK DOWN STAGE # 3 PERFS @ 4897 PSI, 9.9 BPM, 5 BBLS PUMPED. EST INJ RATE 36.1 BPM, 4885 PSI. STEP RATE TEST 20 OPEN PERFS. I.S.I.P. 4139 PSI. F.G. .85, 5 MIN 3977 PSI, 10 MIN 3906 PSI. TREATED PERFS W/ 5000 GALS 15% HCL ACID. PUMPED 3000 LBS 100 MESH IN 1/2 PPG STAGE AND 150500 LBS TLC 30/50. IN .5#, 1#, 2# AND 3# STAGES. AVG RATE 74.1 BPM, MAX RATE 75.9 BPM. AVG PRESS 5156, MAX PRESS 7024. I.S.I.P. 3572 PSI. F.G. .789. SHUT WELL IN 3881 BBLS TO RECOVER. TURNED WELL OVER TO WIRELINE
	8:00 10:00	2.00	STG04	21		P		RIH W/ WIRELINE CBP WAS FLOATING IN GEL, PULLED ABOVE LINER TOP WAIT 40 MINS. RIH SET CBP @ 9854' W/ 4000 PSI. PERFORATED STAGE # 4 FROM 9839' TO 9605'. ALL PERFS CORRELATED TO CUTTERS RADIAL CBL, GAMMA RAY, CCL LOG RUN #1 DATED 04-MAY-2015. 23 NET FT. 69 SHOTS. 2 3/4" GUNS, 16 GM CHARGES, 3 SPF, 120 PHASING. STARTING PRESSURE 4000 PSI. FINAL PRESSURE 4000 PSI. TURNED WELL OVER TO FRAC CREW
	10:00 11:30	1.50	STG04	35		P		PRESSURE TEST LINES @ 9514 PSI. OPENED UP WELL W/ 3935 PSI. BREAK DOWN STAGE # 4 PERFS @ 5417 PSI, 9.8 BPM, 9 BBLS PUMPED. EST INJ RATE 32.5 BPM, 4720 PSI. STEP RATE TEST 20 OPEN PERFS. I.S.I.P. 4020 PSI. F.G. .85, 5 MIN 3971 PSI, 10 MIN 3944 PSI. TREATED PERFS W/ 5000 GALS 15% HCL ACID. PUMPED 3000 LBS 100 MESH IN 1/2 PPG STAGE AND 150600 LBS TLC 30/50. IN .5#, 1#, 2# AND 3# STAGES. AVG RATE 73.3 BPM, MAX RATE 75.5 BPM. AVG PRESS 4896, MAX PRESS 6393. I.S.I.P. 4110 PSI. F.G. .856. SHUT WELL IN 3887 BBLS TO RECOVER. TURNED WELL OVER TO WIRELINE
	11:30 12:45	1.25	STG05	21		P		RIH SET CBP @ 9588' W/ 4100 PSI. PERFORATED STAGE # 5 FROM 9573' TO 9327'. ALL PERFS CORRELATED TO CUTTERS RADIAL CBL, GAMMA RAY, CCL LOG RUN #1 DATED 04-MAY-2015. 21 NET FT. 63 SHOTS. 2 3/4" GUNS, 16 GM CHARGES, 3 SPF, 120 PHASING. STARTING PRESSURE 4100 PSI. FINAL PRESSURE 3800 PSI. TURNED WELL OVER TO FRAC CREW
	12:45 14:15	1.50	STG05	35		P		PRESSURE TEST LINES @ 9557 PSI. OPENED UP WELL W/ 3750 PSI. BREAK DOWN STAGE # 5 PERFS @ 4112 PSI, 9.7 BPM, 9 BBLS PUMPED. EST INJ RATE 34.5 BPM, 4400 PSI. STEP RATE TEST 23 OPEN PERFS. I.S.I.P. 3663 PSI. F.G. .82, 5 MIN 3554 PSI, 10 MIN 3519 PSI. TREATED PERFS W/ 5000 GALS 15% HCL ACID. PUMPED 3000 LBS 100 MESH IN 1/2 PPG STAGE AND 150700 LBS TLC 30/50. IN .5#, 1#, 2# AND 3# STAGES. AVG RATE 73.6 BPM, MAX RATE 75.5 BPM. AVG PRESS 4886, MAX PRESS 6016. I.S.I.P. 3507 PSI. F.G. .804. SHUT WELL IN 3915 BBLS TO RECOVER. TURNED WELL OVER TO WIRELINE
	14:15 15:30	1.25	STG06	21		P		RIH SET CBP @ 9312' W/ 4000 PSI. PERFORATED STAGE # 6 FROM 9297' TO 9073'. ALL PERFS CORRELATED TO CUTTERS RADIAL CBL, GAMMA RAY, CCL LOG RUN #1 DATED 04-MAY-2015. 22 NET FT. 66 SHOTS. 2 3/4" GUNS, 16 GM CHARGES, 3 SPF, 120 PHASING. STARTING PRESSURE 4000 PSI. FINAL PRESSURE 3200 PSI. TURNED WELL OVER TO FRAC CREW



## 2.1 Operation Summary (Continued)

Date	Time Start-End	Duration (hr)	Phase	Activity	Sub	OP Code	MD from (ft)	Operation
	15:30 16:45	1.25	STG06	35		P		PRESSURE TEST LINES @ 9550 PSI. OPENED UP WELL W/ 3414 PSI. BREAK DOWN STAGE # 6 PERFS @ 5916 PSI, 19.7 BPM, 20 BBLS PUMPED. EST INJ RATE 35 BPM, 4834 PSI. STEP RATE TEST 16 OPEN PERFS. I.S.I.P. 3652 PSI. F.G. .83, 5 MIN 3053 PSI, 10 MIN 2930 PSI. TREATED PERFS W/ 5000 GALS 15% HCL ACID. PUMPED 3000 LBS 100 MESH IN 1/2 PPG STAGE AND 150620 LBS TLC 30/50. IN .5#, 1#, 2# AND 3# STAGES. AVG RATE 74.4 BPM, MAX RATE 76 BPM. AVG PRESS 4964, MAX PRESS 6412. I.S.I.P. 3401 PSI. F.G. .803. SHUT WELL IN 3876 BBLS TO RECOVER. TURNED WELL OVER TO WIRELINE
	16:45 19:30	2.75	STG07	21		P		RIH W/ WIRELINE CBP WAS FLOATING IN GEL, PULLED ABOVE LINER TOP WAIT 40 MINS. RIH SET CBP @ 9054' W/ 2700 PSI. PERFORATED STAGE # 7 FROM 9039' TO 8783'. ALL PERFS CORRELATED TO CUTTERS RADIAL CBL, GAMMA RAY, CCL LOG RUN #1 DATED 04-MAY-2015. 23 NET FT. 69 SHOTS. 2 3/4" GUNS, 16 GM CHARGES, 3 SPF, 120 PHASING. STARTING PRESSURE 2700 PSI. FINAL PRESSURE 2500 PSI. SHUT IN WELL. CLOSED AND LOCKED ALL FRAC VALVES. CLOSED IN SURFACE CSG W/ TWO VALVES.
5/14/2015	6:00 7:30	1.50	STG07	28		P		CREW TRAVEL HELD SAFETY MEETING ON PUMPING HIGH PRESSURE AND TESTING LINES. FILLED OUT JSA
	7:30 9:15	1.75	STG07	35		P		PRESSURE TEST LINES @ 9569 PSI. OPENED UP WELL W/ 1815 PSI. BREAK DOWN STAGE # 7 PERFS @ 3369 PSI, 9.9 BPM, 16 BBLS PUMPED. EST INJ RATE 35.1 BPM, 3950 PSI. STEP RATE TEST 20 OPEN PERFS. I.S.I.P. 2991 PSI. F.G. .77, 5 MIN 2364 PSI, 10 MIN 2159 PSI. TREATED PERFS W/ 5000 GALS 15% HCL ACID. PUMPED 3000 LBS 100 MESH IN 1/2 PPG STAGE AND 150650 LBS WHITE 30/50. IN .5#, 1#, 2# AND 3# STAGES. AVG RATE 74.3 BPM, MAX RATE 75.6 BPM. AVG PRESS 4149, MAX PRESS 5134. I.S.I.P. 3605 PSI. F.G. .838. SHUT WELL IN 3981 BBLS TO RECOVER. TURNED WELL OVER TO WIRELINE
	9:15 11:15	2.00	STG08	21		P		RIH SET CBP @ 8761' W/ 2900 PSI. PERFORATED STAGE # 8 FROM 8746' TO 8587'. ALL PERFS CORRELATED TO CUTTERS RADIAL CBL, GAMMA RAY, CCL LOG RUN #1 DATED 04-MAY-2015. 15 NET FT. 45 SHOTS. 2 3/4" GUNS, 16 GM CHARGES, 3 SPF, 120 PHASING. STARTING PRESSURE 2900 PSI. FINAL PRESSURE 2800 PSI. TURNED WELL OVER TO FRAC CREW
	11:15 12:45	1.50	STG08	35		P		PRESSURE TEST LINES @ 9495 PSI. OPENED UP WELL W/ 2645 PSI. BREAK DOWN STAGE # 8 PERFS @ 3329 PSI, 10 BPM, 10 BBLS PUMPED. EST INJ RATE 36 BPM, 3846 PSI. STEP RATE TEST 23 OPEN PERFS. I.S.I.P. 2971 PSI. F.G. .78, 5 MIN 2698 PSI, 10 MIN 2638 PSI. TREATED PERFS W/ 5000 GALS 15% HCL ACID. PUMPED 2800 LBS 100 MESH IN 1/2 PPG STAGE AND 150160 LBS WHITE 30/50. IN .5#, 1#, 2# AND 3# STAGES. AVG RATE 74.1 BPM, MAX RATE 75.8 BPM. AVG PRESS 4539, MAX PRESS 5655. I.S.I.P. 3277 PSI. F.G. .811. SHUT WELL IN 3948 BBLS TO RECOVER. CLOSED IN WELL CLOSED AND LOCKED ALL FRAC VALVES. CLOSED SURFACE CSG W/ 2 VALVES.
	12:45 16:30	3.75	RDMO	02		P		RD FRAC EQUIPMENT AND MOVE OFF LOCATION.
	16:30 19:00	2.50	MIRU	01		P		MOVE IN AND PARTIALLY RU 2" COIL TUBING UNIT SDFN.
5/15/2015	6:00 6:30	0.50	CTU	28		P		CREW TRAVEL HELD SAFETY MEETING RIGGING UP COIL TBG (PINCH POINTS). FILLED OUT JSA.
	6:30 8:30	2.00	CTU	18		P		FINISHED RIGGING UP COIL TUBING, MADE UP DRILLOUT ASSEMBLY W/ 4 1/8 JZ ROCK BIT. FUNCTION TEST MOTOR. PRESSURE TEST COIL, LUBRICATOR AND FLOWBACK LINES TO 9000 PSI. HELD.

## 2.1 Operation Summary (Continued)

Date	Time Start-End	Duration (hr)	Phase	Activity	Sub	OP Code	MD from (ft)	Operation
	8:30 20:30	12.00	CTU	10		P		RIH PUMPING 1 BPM AND RETURNING 1 BPM, TO LINER TOP @ 8300'. INCREASED RATE TO PUMPING 2.5 BPM RETURNING 3.5 BPM. DRILLED OUT CBPs @ 8761', 9054', 9312', 9588', 9854', 10195', 10528' AND 10550'. CIRCULATE ON BTM FOR 1 HR, TOOH TO LINER TOP CIRCULATE FOR 1HR. TOOH . BUMPED UP.
	20:30 22:30	2.00	RDMO	02		P		LD DRILLOUT ASSEMBLY, RD COIL TUBING, CLOSED TOP HCR VALVE INSTALLED NIGHT CAP. BLEW COIL TBG DRY. TURNED WELL OVER TO FLOWBACK CREW.
	22:30 22:35	0.08	FB	17		P		OPEDED WELL @ 2500 PSI ON 12/64 CHOKE
	22:35 6:00	7.42	FB	19		P		2200 PSI ON 12/64 CHOKE. RECOVERED 0 MCF, 0 BBLS OIL AND 449 BBLS H2O.
5/16/2015	6:00 6:30	0.50	FB	19		P		HELD SAFETY MEETING ON FLOWBACK PROCEDURES FILLED OUT JSA,
	6:30 6:00	23.50	FB	19		P		2000 PSI ON 12/64 CHOKE. RECOVERED 0 MCF, 0 BBLS OIL AND 1521 BBLS H2O
5/17/2015	6:00 6:30	0.50	FB	28		P		HELD SAFETY MEETING ON FLOWBACK PROCEDURES. FILLED OUT JSA.
	6:30 6:00	23.50	FB	19		P		1900 PSI ON 12/64 CHOKE. RECOVERED 38 MCF, 49 BBLS OIL AND 915 BBLS H2O.
5/18/2015	6:00 6:30	0.50	FB	28		P		HELD SAFETY MEETING ON FLOWBACK PROCEDURES. FILLED OUT JSA
	6:30 6:00	23.50	FB	19		P		1900 PSI ON 12/64 CHOKE. RECOVERED 122 MCF, 176 BBLS OIL AND 557 BBLS H2O.
5/19/2015	6:00 7:30	1.50	WLWORK	28		P		CREW TRAVEL HELD SAFETY MEETING ON WIRELINE SAFETY (OVERHEAD HAZARDS) FILLED OUT JSA.
	7:30 9:45	2.25	WLWORK	20		P		RU WIRELINE. PRESSURE TEST LUBRICATOR TO 5000 PSI HELD, RIH SET PKR W/ PLUG CATCHER @ 8400' W/ 1900 PSI. SETTING TOOL DIDN'T SHEAR OFF PKR.
	9:45 12:30	2.75	WLWORK	20		N		bled well down to 1100 PSI. SHUT IN WELL TRIED TO PULL OFF PKR. PRESSED UP TO 1900 ON CSG. TRIED WORKING SETTING TOOL FREE. PULLED OUT OF ROPE SOCKET. BLEED DOWN WELL RD WIRELINE RECOVERED 110 MCF, 64 BBLS OIL, 148 BBLS H2O.
	12:30 14:30	2.00	WLWORK	42		N		WAIT ON BRAIDED LINE TRUCK.
	14:30 21:00	6.50	BL	52		N		RU BRAIDED LINE. RIH W/ 3 1/8" OVERSHOT W/ 1 7/16" GRAPPLE, OIL JARS, SPANGE BARS AND WEIGHT BARS, ENGAGED FISH PRESSURED UP CSG TO 1900 PSI. JARRED ON FISH. CAME FREE PULLED OUT W/ FISHING ASSEMBLY AND FISH (WEIGHT BARS CCL AND SETTING TOOL). RD BRAIDED LINE TRUCK. CLOSED IN WELL. CLOSED AND LOCKED ALL FRAC VALVES.
5/20/2015	6:00 7:30	1.50	MIRU	28		P		CREW TRAVEL HELD SAFETY MEETING ON RIGGING UP RIG. FILLED OUT JSA.
	7:30 8:30	1.00	MIRU	01		P		MIRU SERVICE RIG. 200 CSIP BLEED DOWN WELL.
	8:30 10:00	1.50	WOR	16		P		ND GOAT HEAD, 5" HCR VALVE, CROSS FLOW, 5" HCR VALVE AND SPOOL. NU 5K BOP ON TOP OF 7" MANUAL FRAC VALVE.
	10:00 14:30	4.50	WOR	39		P		RIH W/ ON OFF TOOL, 5-JTS 2 3/8 L-80 EUE TBG, X-OVER AND 253-JTS 2 7/8 L-80 EUE TBG LATCHED ONTO PKR @ 8385' TBG TALLY LD 1-JT 2 7/8 , SPACED OUT TBG W/ 1-10', 1-2' X 2 7/8 N-80 EUE TBG SUBS.
	14:30 16:30	2.00	WOR	06		P		CIRCULATE WELL WITH 360-BBLS PKR FLUID.

## 2.1 Operation Summary (Continued)

Date	Time Start-End	Duration (hr)	Phase	Activity	Sub	OP Code	MD from (ft)	Operation
	16:30 18:30	2.00	WOR	16		P		LANDED TBG W/ 6' 2 7/8 TBG SUB UNDER HANGER W/ BPV. IN TBG HEAD. ND BOP REMOVED BPV. REMOVED HANGER AND 6' TBG SUB. LANDED TBG W/ HANGER AND BPV IN TBG HEAD. NU WELLHEAD. PRESSURE TEST WELLHEAD 5000 PSI. PRESSURE TEST FLOW BACK LINE 4000 PSI. REMOVE BPV. PUMP OUT PLUG @ 2900 PSI.
	18:30 19:30	1.00	RDMO	02		P		OPENED WELL 1800 PSI ON 14/64 CHOKE. RD RIG.
	19:30 19:30	0.00	FB	19		P		2100 PSI ON 14/64 CHOKE. RECOVERED 43 MCF, 140 BBLS OIL AND 185 BBLS H2O.

Table of Contents

1	General.....	1
1.1	Customer Information.....	1
1.2	Well Information.....	1
2	Summary.....	1
2.1	Operation Summary.....	1